

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company. FRONTIER OIL CO.
Farm. Kirkman No. 2

SEC. 20 T. 19 R. 13W
C W/2 SE NW

Total Depth. 3460
Comm. 1-15-56 Comp. 1-27-56

County Barton
KANSAS

Shot or Treated.
Contractor. Kiefer & Krause Drilling Co., Inc.
Issued. 4-14-56



CASING:
8 5/8 @ 777' w/ 400 sx cmt.
5 1/2 @ 3459' w/ 100 sx cmt.

Elevation. 1857 DF

Production. 78 BOPD

Figures indicate Bottom of Formations.

sand	135
shale	320
sand	460
red bed	550
shale	685
red bed	760
lime & red bed	765
anhydrite	798
shale & shells	1515
shale	1660
shale & lime	1725
shale & shells	1790
lime	2000
shale & lime	2100
shale & shells	2200
shale	2330
shale & shells	2540
shale	2629
shale & shells	2755
lime	2835
shale	2850
shale & shells	2978
lime	3460
Total Depth	

TOPS:	
Anhydrite	765
Heebner	3073
Brown lime	3170
Lansing-K. C.	3181
Conglomerate	3400
Arbuckle	3433