


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HONAKER DRILLING CO., INC.
Farm- Gunn No. 1

SEC. 20 T. 19 R. 13W
NE NE SE

Total Depth. 3441'
Comm. 2-24-55 Comp. 3-10-55
Shot or Treated.
Contractor.
Issued. 6-4-55

County Barton
KANSAS



CASING:
8 5/8" 755' w/375 sx cem.
5 1/2" 3440' w/150 sx cem.

Elevation. 1855 RB

Production. 165 BO

Figures indicate Bottom of Formations.

clay	20
sand-gravel	175
shale-shells	300
sand	340
shale-shells	430
red bed	505
shale-red bed	746
Anhydrite	785
shale-shells	1370
salt-shale	1450
lime-shale	1460
shale-lime strks	1650
lime	2165
shale-lime strks	2310
shale-shells	2530
shale-lime	3184
lime	3392
shaley Conglomerate	3417
Conglomerate	3441
Total Depth RTD	

TOPS:

Heebner	3061
Brown Lime	3159
Lansing-Kansas City	3171
Chert Conglomerate	3402
Arbuckle	3439

DST #1: 3175-3184 - Bee
Testers Tool Tool open
15" - Blow 1" - Red. 5' mud.

DST #2 - 3184-3202 - Bee
Testers Tool. Open 1 hr.
Closed 20" Blow: Fair 10"-
weak - 38". Rec. 105' S.O.C.M.
Pressure 50#.

DST #3 - 3338-3368 Bee
Testers Tool. Open 1 hr.-
closed 20". Blow: Gas in
33". Rec. 300' froggy oil,
270' oil. Bottom hole Pres-
sure: IFP 50#, FFP 275#, BHP
400#.