


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HONAKER DRILLING, INC.
Farm-McKinney No. 1

SEC. 20 T. 19 R. 13W
SE SW NE

Total Depth. 3453.5
Comm. 3-10-55 Comp. 3-21-55
Shot or Treated.
Contractor. Honaker Drilling, Inc.
Issued. 6-25-55

County Barton
KANSAS



Elevation. 1855 RB

Production. 168 BO

CASING:

8 5/8 @ 758' w/ 375 sx cmt.
5 1/2 @ 3448' w/ 150 sx cmt.

Figures indicate Bottom of Formations.

clay & sand	50
shale & shells	305
sand	320
Dakota sand	340
clay & shale	425
red bed	575
red bed & shale	750
Anhydrite	795
shale & shells	1330
salt & shale	1450
shale & lime	3253
lime	3357
lime & conglomerate	3425
lime	3440
conglomerate	3448
lime	3453.5
Total Depth	

TOPS:

Heebner	3050
Brown lime	3158
Lansing-KC	3170
Cherty conglomerate	3398
Arbuckle	3445

DST #1: 3296-3308, open 1 hr. good
blow rec. 240' gas, 630' water

DST #2: 3337-57, open 25 min. wk. blow
12 min. rec. 40' mud, BHP 675#

DST #3: 3424-40, open 1 hr. good blow
rec. 210' HO&GCM, 120' oil, 900' gas
in pipe, BHP 170#