

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HONAKER DRILLING, INC. et al
Farm- McKinney No. 2

SEC. 20 T. 19 R. 13W
C S/2 SE NE

Total Depth. 3447
Comm. 8-18-55 Comp. 8-29-55
Shot or Treated.
Contractor. Honaker Drilling, Inc.
Issued. 1-7-56

County Barton
KANSAS



Elevation. 1855 RB

Production. 222 BOPD

CASING:

8 5/8 @ 763' w/ 400 sx cmt.
5 1/2 @ 3443' w/ 125 sx cmt.

Figures indicate Bottom of Formations.

top soil & clay	20
sand & gravel	150
blue shale	290
sand	370
shale & shells	495
shale & red bed	750
anhydrite	780
red bed & shale	1060
shale & shells	1290
salt & shale	1475
lime & shale	3170
lime	3250
lime & shale	3355
lime	3374
lime & shale	3445
lime	3447
Total Depth	

RTD

TOPS:

Heebner	3065
Brown lime	3160
Lansing-K. C.	3170
Cherty conglomerate	3403
Arbuckle	3442

DST #1: 3176-88, open 1 hr. SI 30 min. wk. bl. 10 min. vac. booster 15 min. SI on vac. 15 min. rec. 100' gas, 20' GCM w/ fine specks oil, BHP 0#.

DST #2: 3303-13, open 45 min. SI 30 min. wk. bl. 4 min. vac. booster 15 min. SI on vac. 15 min. rec. 3' mud BHP 0#.

DST #3: 3354-74, open 30 min. SI 20 min. gas in 21 min. rec. 375' oil.