

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- HULME DRILLING CO.
Farm- Feldman No. 1

SEC. 26 T. 19 R. 13W
SW SE SW

Total Depth. 3485
Comm. 6-29-55 Comp. 7-9-55
Shot or Treated.
Contractor. Greenland Drilling Co.
Issued. 8-27-55

County Barton

KANSAS



Elevation. 1839 DF

Production. Dry

CASING:

8 5/8 703' w/ 375 sx cmt.

Figures Indicate Bottom of Formations.

sand, gravel & clay	110
shale & shells	279
shale w/ sand streaks	319
red bed w/ sand streaks	365
red bed	480
red bed, shale & shells	693
anhydrite	715
shale & shells	755
shale & red shale w/ shells	970
shale w/ shells	1120
shale & shells w/ salt	1420
sandy shale & lime	1515
lime & shale	2100
shale	2135
lime	2220
shale & lime	2430
shale	2495
lime streaks in shale	2575
lime	2600
lime & shale	3045
shale & sandy lime	3060
sandy shale w/ lime streaks	3148
lime	3155
shale	3162
lime	3396
conglomerate	3428
lime & chert	3453
Arbuckle	3468
cherty lime	3485
Total Depth	

TOPS:

Anhydrite	695
Heebner	3036
Brown lime	3148
Lansing	3160
Base KC	3388
Arbuckle	3428

DST #1: 3165-3238, open 1 hr. good blow; rec. 122' SO&GCM, IFP 75#, FFP 100#, BHP 1000#/20 min.

DST #2: 3433-53, open 1 hr. wk. bl. thruout, rec. 55' HOCM, BHP 80#/20 min.

DST #3: 3453-58, open 1 hr. wk. bl. 13 min. rec. 30' OCM, BHP 0#/20 min.

DST #4: 3458-68, open 30 min. wk. bl. 14 min. rec. 30' OCM, BHP 475#/20 min.

DST #5: 3470-85, open 30 min. strong blow; rec. 1380' SW, IFP 50#, FFP 600#, BHP 1100#/20 min.