

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. CHAS. HULME DRILLING CONTRACTOR
Farm. Hammond No. 1

SEC. 26 T. 19 R. 13W
E/2 E/2 SW

Total Depth. 3500

Comm. 4-5-55

Comp. 4-18-55


Shot or Treated.

Contractor. Chas. Hulme Drilling Contractor

Issued. 7-30-55

County Barton

KANSAS



Elevation. 1839 RB

Production. 143 BOPD

CASING:

8 5/8 @ 400' w/ 250 sx cmt.
5 1/2 @ 3499' w/ 100 sx cmt.

Figures indicate Bottom of Formations.

clay	30	DST #7: 3445-55, open 1 hr., fair
gravel	45	blow thruout, rec. 2250' gas, 160'
sand & gravel	140	muddy oil, BHP 725#/20 min.
shale & shells	298	
Dakota sand	350	Ran Halliburton Guard Log.
red bed	693	
anhydrite	716	
shale	1010	
shale & shells	1155	
salt	1370	
shale & shells	1580	
lime	1870	
shale & shells	1905	
lime	2085	
lime & shale	2410	
shale & shells	2610	
shale & lime	2715	
lime	3065	
sandy shale	3148	
lime	3235	
sand & lime	3374	
lime	3375	
chert	3416	
lime	3500	
Total Depth		

TOPS:

Anhydrite	693
Heebner	3035
Brown lime	3148
Lansing	3160
Conglomerate	3394
Arbuckle	3418

DST #1: 3210-35, open 1/2 hr., weak
blow 10 min., rec. 180' SOCM, BHP 0#

DST #2: 3347-75, open 1/2 hr., weak
blow 1 min., rec. 85' SOCM, BHP 0#

DST #3: 3419-22, open 1/2 hr., weak
blow 7 min., rec. 15' mud, NSO, BHP
75#/20 min.

DST #4: 3422-26, open 1/2 hr., gas to
surf. 8 min. (est 50 MCFG) rec. 15'
GCM, BHP 1100#/20 min.

DST #5: 3426-30, open 1 hr., gas to
surf. 14 min., (est. 50 MCFG) rec.
20' GCM, BHP 1100#/20 min.

DST #6: 3431-35, open 1 hr., gas to
surf. 28 min., rec. 15' GCM, BHP 375#/
20 min.