


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- W. L. HARTMAN
Farm- Slentz No. 1

SEC. 27 T. 19 R. 13W
SW NE NE

Total Depth. 3496'
Comm. 3-24-56 Comp. 4-6-56
Shot or Treated.
Contractor. H & H Drlg. Co.
Issued. 6-23-56

County Barton
KANSAS



CASING:

8 5/8" 417' cem w/275 sx
5 1/2" 3495' cem w/150 sx

Elevation. 1848' RB

Production. 87 BOPD

Figures indicate Bottom of Formations.

clay and sand	40
sand	220
shale	285
sand	320
shale	417
red bed and shale	710
shale & shells	1245
salt	1494
shale & shells	1545
shale & lime	2830
lime	3395
chert & shale	3444
dolomite	3496 RTD
Total Depth	

Tops:	
Topeka	2798
Heebner	3037
Base Oread	3074
Brown Lime	3144
Lansing	3157
Base Kansas City	3392
Conglomerate	3395
Arbuckle	3444