

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- CHAS. HULME DRILLING CONTRACTOR
Farm Moses Estate No. 1

SEC. 27 T. 19 R. 13W
NE SE SE

Total Depth. 3500

Comm. 8-6-55

Comp. 8-30-55

Shot or Treated.

Contractor. Chas. Hulme Drilling Contractor

Issued. 11-5-55

County Barton

KANSAS



Elevation. 1845 RB

Production. 85 BOPD

CASING:

8 5/8 @ 715' w/ 400 sx cmt.
5 1/2 @ 3499' w/ 100 sx cmt.

Figures indicate Bottom of Formations.

clay & sand	190
clay	270
sand & clay	350
clay & shale	704
anhydrite	730
red bed	765
red bed & shale	1515
lime	1630
shale & lime	1780
lime	1840
lime & shale	2000
lime	2160
lime & shale	2400
shale	2560
lime, shale & shells	2706
lime & shale	2803
lime	3090
sand & shale	3158
lime	3397
lime & chert	3440
lime	3500
Total Depth	

TOPS:

Anhydrite	704
Heebner	3044
Toronto	3063
Brown lime	3157
Lansing	3169
Conglomerate	3404
Arbuckle	3438

DST #1: 3213-46, open 30 min. wk. bl.
8 min. rec. 25' mud w/ few specks oil,
BHP 575#/15 min.

DST #2: 3355-97, open 30 min. wk. bl.
12 min. rec. 30' mud, no show, BHP
375#/20 min.

DST #3: 3438-44 (run#1) packer failed
Run #2. 3443-49; packer failed
Run #3: 3440-49, open 30 min. wk. bl.
5 min. rec. 85' mud, no show, BHP
725#/15 min.

DST #4: 3449-62, open 1 hr. gas to
surf 10 min. rec. 1290' gassy oil,
IFP 125#, FFP 375#, BHP 800#/20 min.