

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- JOE J. HONAKER
Farm- Honaker No. 1

SEC. 28 T. 19 R. 13W
NW SW NE NE
900' fr NL 1480' fr WL NE/4

Total Depth. 3453
Comm. 12-2-53 Comp. 12-13-53
Shot or Treated.
Contractor. Honaker Drlg. Co.
Issued. 1-16-54

County Barton
KANSAS



CASING:
8 5/8" 740' cem. w/425 sx

Elevation. 1848 BB

Production. Dry

Figures indicate Bottom of Formations.

sand & gravel	130
shale blue	290
Dakota sand	315
shale blue	355
red bed	535
red bed & shale	660
red bed & shale blue	727
anhydrite	785
red bed	820
shale & sholls	1300
salt & shale	1380
shale & shells	1520
lime & shale	3179
lime	3453 RTD
Total Depth	

Tops:
Anhydrite 727
Topeka 2823
Heebner 3058
Lansing 3170
Conglomerate 3414

DST : 3173-3185' tool open
30 mins. weak blow for 7 mins.
rec. 10' mud. No show of oil.
BHP 0.

DST: 3291-3350' tool open
20 mins. fair blow throughout
test. rec. 30' very slightly
oil and gas cut mud. BHP 240#
in 20 mins.