


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HILTON DRILLING, INC.
Farm- Allied Builders No. 4

SEC. 28 T. 19 R. 13W
NE NE NE
250 NL, 150 EL

Total Depth. 3472'
Comm. 1-18-54 Comp. 2-1-54
Shot or Treated.
Contractor.
Issued. 8-28-54

County Barton
KANSAS



CASING:
8 5/8" 739' cen w/400 sx
5" 3400'

Elevation. 1816' DF

Production. Flow 286 BO & NW

Figures Indicate Bottom of Formations.

surface soil	90
sand strks, clay blue	170
sand & shale	415
red bed & shale	730
anhydrite	755
red bed	765
red bed, & shale	860
shale & shells	1180
shale & salt	1320
shale & shells	1550
lime brkn & sdy	1565
lime	1685
lime brkn & shale	1870
shale & lime	2100
shale, lime & shells	2170
lime & shale	2300
lime broken & shale	2430
shale & shells	2460
shale & lime	2818
lime	3045
lime & shale	3077
shale	3146
lime brn	3158
Kansas City lime	3190
lime	3388
Conglomerate	3415
Conglomerate chert	3445
Conglomerate	3455
reworked Arbuckle	3472 RTD
Total Depth	

Tops: K.B.
Anhydrite 730-755 (drillers)
Topeka 2813
Heebner Shale 3046
Toronto Lime 3057
Douglas 3076
Brown Lime 3146
Lensing-Kansas City 3158
Conglomerate 3387

DRILL STEM TESTS:

#1 3222-34, open 9 min, gas to surface
in 3 min. oil to surface in 9 min.
IFP 550#, FFP 790#, BHP 1140# in 30 min.