

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - VICKERS PETRO.CO., INC.
Farm - Kent No. 1.

SEC. 31 T. 19 R. 13 W
N W C NE

Total Depth. 3530'
Comm. 1-9-44 Comp. 1-22-44
Shot or Treated.
Contractor.
Issued. 2-12-44

County. Barton
KANSAS



CASING:
10 $\frac{3}{4}$ " 773' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand	0-130
shale	340
sand & red bed	475
red bed & shale	762
anhydrite	773
red bed & shale	985
salt & shale	1100
shale & shells	1590
shale & lime	2248
shale	2605
lime	2620
lime & shale	2866
lime	3104
lime & shale	3198
lime	3395
lime & shale	3430
conglomerate	3476
Arbuckle dolomite	3530
Total Depth.	

Tops:	
Anhydrite	762-773
Ft. Riley	1807
Florence Flint	1915
Topeka	2847
Heebner	3104
Base Oread	3126
Lansing (Brown)	3184
Lansing (White)	3198
Base K. C.	3401
Cherty Congl.	3430
Arbuckle	3476

3278-3301 break-good porosity
no shows
3476-3513 scattered live &
dead shows / some odor
3513 water