

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas

Company - REPUBLIC NATURAL GAS COMPANY
Farm - Koopman No. 1

SEC. 35 T. 19 R. 13W
NW SW NE

Total Depth. 3520
Comm. 5-24-50 Comp. 6-17-50
Shot or Treated.
Contractor. W. L. Hartman
Issued. 7-15-50

County. Barton
KANSAS



CASING:
8 5/8" OD 200' com. w/250 sx, circ.
5 1/2" OD 3516' com. w/75 sx

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	175
shale blue	200
redbed	515
shale	692
Anhydrite	707
sand & shale	870
sand	1250
salt	1280
shale & sand	1380
salt & shells	1500
limo	1580
limo & shale	1621
limo	1650
limo & shale	1852
shale & shells	2005
limo & shale	2085
shale & shells	2152
limo	2272
limo & shale	2430
shale	2587
limo & shale	2750
shale	2830
shale & limo	2958
limo	3042
Heobner shale	3050
shale & limo	3196
shale	3257
limo	3442
limo, Arbucklo	3455
Arbucklo limo & chert	3478
Arbucklo limo	3520
Total depth	

Scout Tops:

Anhydrite	690
Topoka	2798
Lansing	3173
BKC	3390
Conglomerate	3403
Arbucklo	3435

Note: Drill pipe when laid
down measured 3517' and 5 1/2" OD
Csg measured TD to be 3517'.