


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MARMAD OIL COMPANY
Farm- Sutton No. 1

SEC. 15 T. 19 R. 14W
NE SW SW

Total Depth. 3506
Comm. 2-29-52 Comp. 3-20-52
Shot or Treated.
Contractor. Fleming & Woodman Drlg Co.
Issued. 6-28-52

County Barton
KANSAS



Elevation. 1884

Production. Est Pmp 50 bbls & no water

Figures Indicate Bottom of Formations.

shale, shells	160
shale	303
sand, shale	520
red bed, shale	812
red bed	816
anhydrite	836
red bed	965
red bed, shale	1420
shale, lime	1700
shale, shells	1820
lime, shale	1850
lime	1990
lime, shale	2100
lime	2188
shale	2215
shale, lime	2250
shale	2500
shale, shells	2785
lime, shale	2890
lime	3465
lime, shale	3485 RTD

CABLE TOOLS.
conglomerate? 3506
Total Depth

Tops: Scout.
Heebner 3112
Brown Lime 3198
Kansas City 3212
Conglomerate 3450

Lane-Wells logging well.
Perf. & acidize by Dowell
1000 gals. swabbed down
and tested.

D.S.T. 3267, Tool open 35 min.
30' oil cut mud. BHP zero.

Run Johnson Tester 3344-55?
O.B. Tool open 1 hr. Rec.
270' oil & gas cut mud BHP 1150#
open 15 min.