


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- LEE PHILLIPS ET AL  
Farm- Merten "B" No. 1

SEC. 18 T. 19 R. 11W  
NE NE NE

Total Depth. 3605'  
Comm. 4-21-56 Comp. 5-2-56  
Shot or Treated.  
Contractor. Ben F. Brack Oil Co.  
Issued. 6-9-56

County Barton  
KANSAS



CASING:  
8 5/8" 868'

Elevation. 1913' DE

Production. Dry

Figures indicate Bottom of Formations.

surface clay & sand	85
shale, shells & sand	240
shale	320
sand	385
shale & sand	625
shale & shells	860
anhydrite	900
shale & shells	1660
lime & shale	1705
lime	2030
lime & shale	2100
shale & lime	2380
lime & shale	2520
shale & lime	2650
lime & shale	2850
lime	2965
lime & shale	3042
lime	3144
lime & shale	3186
shale & lime	3295
lime	3605
Total Depth	

Tops:	
Heebner	3155
Brown Lime	3228
Lansing-Kansas City	3249
Conglomerate	3509
Arbuckle	3586

DST #1 open 1 hr., rec. 450' gas & 30'  
HOCM. BHP 860#.