

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SKELLY OIL CO.
Farm. Great Bend No. 1

SEC. 24 T. 19 R. 14W
SW SE SE
990' fr EL, 330' fr SL, SE/4

Total Depth. 3506
Comm. 10-30-55 Comp. 11-11-55
Shot or Treated.
Contractor. Claude Wentworth Drilling Co., Inc.
Issued. 12-24-55

County Barton
KANSAS



CASING:

8 5/8 @ 780' w/ 450 sx cmt.

Elevation. 1864 DF

Production. Dry

Figures indicate Bottom of Formations.

surface soil, sand & shale	295
shale; sand & red bed	710
shale, shells & red bed	770
anhydrite	795
red bed, shale & shells	1235
shale, shells & salt	1360
shale & shells	1650
lime & shale	3202
buff finely crystalline lime	3204
lime	3210
buff fine crystalline, finely oolitic lime	3212
lime	3251
light gray fine crystalline oolitic lime	3261
lime	3320
light gray fine crystalline lime	3338
lime	3345
lime & shale	3492
light gray, medium to coarse crystalline dolomite	3496
light gray to buff medium to coarsely crystalline dolomite	3506
Total Depth	

DST #5: packer @ 3496, 10' anchor, open 1 hr., fair bl. thruout, rec. 155' SW, BHP 970#

Ran Halliburton Gamma Ray Guard Log

TOPS:

Anhydrite	773
Base Anhydrite	796
Wellington	1230
Base Wellington	1637
Neva	2196
Tarkio	2555
Topeka	2753
Heebner	3092
Toronto	3108
Douglas sand	3124
Brown lime	3191
Lansing	3202
Conglomerate	3420
Arbuckle	3490

DST #1: packer @ 3193, 25' anchor, open 1 hr. rec. 15' VSOCM, BHP 12#

DST #2: packer @ 3248, 27' ancor, open 1 hr. wk. bl thruout, rec. 35' WCM w/ few specks oil, BHP 895#

DST #3: packer @ 3315, 30' anchor, open 1 hr, rec. 8' mud, no oil or gas, wk. bl 10 min. BHP 22#

DST #4: packer : 3487, 9' anchor, open 1 hr: fair bl. thruout, rec. 100' HOCM, BHP 180#