

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ALLAN ET AL
Farm- Koch No. 1

SEC. 25 T. 19 R. 14W
CS/2 S/2 NE

Total Depth. 3368 D.F.
Comm. 7-22-52 Comp. 8-11-52
Shot or Treated.
Contractor. Tom Allen
Issued. 9-20-52

County Barton KANSAS



Elevation. 1870 DF

Production. 30 BOPD

CASING:

8 5/8" 783' cem. w/275sx
5 1/2" 3324' cem. w/100 sx

Depth from R.B.

Figures Indicate Bottom of Formations.

surface soil	15
sand & gravel	115
shale	290
sand	315
red beds	773
anhydrite	798
red & gry shale	1180
shale gry	1280
shale & salt	1500
shale, salt & anhy.	1600
shale & anhydrite	1740
shale	1760
lime shale	2380
shale & shells	2780
lime & shale	3125
shale & sand	3188
RTD lime w/shale brks	3324
RB 3322 DF	3324
DF lime	3341
DF shale	3344
DF lime	3354
DF shale	3359
DF TD lime	3368
Total Depth	

Tops: RB	
Anhydrite	773
Heebner	3093
Brown Lime	3188
Lansing	3200

Testing:
Show oil 3363 DF
Bail 10 GOPH.
300 gal. acid.
Swab 1 1/2 BOPH
1000 gal. acid
Swab 30 BOPD