

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. HONAKER DRILLING CO., et al
Farm Opie No. 3

SEC. 26 T. 19 R. 14W
SW SE NW

Total Depth. 3499

Comm. 6-4-53

Comp 6-18-53


Shot or Treated.

Contractor. Honaker Drilling Co.

Issued. 8-8-53

County Barton

KANSAS



Elevation. 1874 DF

Production. Pot. 323 BO

CASING:

8 5/8 set at 798' w/ 400 sx cement
5 1/2 set at 3497' w/ 175 sx cement

Figures indicate Bottom of Formations.

sand	230
shale & sand	360
Dakota sand	400
sand & shale	500
red bed & shells	670
red bed & shale	795
anhydrite	810
red bed	900
shale & shells	1435
shale, shells & salt	1580
lime & shale	2952
lime	2989
lime & shale	3200
lime	3205
lime & shale	3465
lime	3499
Total Depth	

TOPS:

Anhydrite	795
Heebner	3084
Dodge	3103
Brown lime	3182
Lansing	3193
Conglomerate	3432
Reworked Arbuckle	3488

DST #1: 3184-3203, open 45 min. weak
blow 13 min. rec. 120' gas, 20' GCM,
BHP Off

DST #2: 3250-64, open 1 hr. weak
blow thruout, rec 225' water. BHP Off

DST #3: 3312-58, open 1 hr. good
blow thruout, rec. 120' O&GCM, 240'
G & MCO, BHP 380# 15 min.

Ran Schlumberger

RTD 3497