

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- HONAKER DRILG. CO., INC.  
Farm- Opie No. 1

SEC. 26 T. 19 R. 11W  
SE SE SW

Total Depth. 3557  
Comm. 12-20-51 Comp. 12-31-51  
Shot or Treated.  
Contractor. Honaker Drilg. Co., Inc.  
Issued. 3-1-52

County Barton  
KANSAS



Elevation. 1875 R.B.

Production. BHB 1272 BO & tr. wtr.

Figures indicate Bottom of Formations.

clay & sand	100
shale & shells	306
sand	335
Dakota sand	390
red bed	470
red rock & shells	685
red bed	695
red bed & iron	715
anhydrite	817
shale & shells	1225
salt	1365
shale & shells	1600
lime & shale	1645
lime	1990
lime & shale	2260
shale & shells	2275
lime & shale	2960
lime	3080
lime & shale	3185
lime	3390
lime & shale	3507
lime	3557 RTD
Total Depth	

Tops:	
Anhydrite	788
Heebner	3008
Brown Lime	3179
Lansing	3191
Chert Congl.	3430
Arbuckle	3516

Ran Gamma Ray log  
Perf. 3526-3529 12 shot rec. 400' SW in 30 min.  
Perf. 3516-3519 10 shots, show of gas cut mud on gun.  
Az. 250 gal.  
Perf. 3357-3361 12 shots small show of oil on gun Perf. 3357-3361 Az. 1000 gal.  
Perf. 3320-24 show of gas in 3 min. gas incr. fast, show of oil on gun. good free oil. Shot 12 more shots 3320 $\frac{1}{2}$  to 3324 $\frac{1}{2}$   
Well filled up 1900' in 40 mins. Az. 1500 gal.

D.S.T. 3225-3242 tool open 45 mins. good blow throughout test. Rec. 110' mud cut oil 28 ins. shut-in press. 390# BHP 390#.  
D.S.T. 3339-3358 tool open 45 mins. weak blow for 30 mins. Rec. 12' mud.