

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- HONAKER DRILLING CO., et al.
Farm- Weber No. 2

SEC. 35 T. 19 R. 14W
NW NE NW

Total Depth. 3395
Comm. 1-10-53 Comp. 1-21-53
Shot or Treated.
Contractor. Honaker Drilling Co.
Issued. 2-21-53

County Barton

KANSAS



Elevation. 1874 DF

Production. Dry

CASING:

8 5/8 799' w/ 425 sx cement

Figures indicate Bottom of Formations.

sand	140
sand & shale	170
shale, clay & sand	280
shale & sand	340
shale	355
sand	400
red bed	540
red bed & shells	690
red bed	794
anhydrite	799
shale & shells	1260
salt	1375
shale & shells	1550
lime & shale	2740
lime	3080
lime & shale	3165
lime	3395
Total Depth	

TOPS:

Anhydrite	794
Heebner	3092
Brown lime	3185
Lansing	3197

WESTERN DRILL STEM TESTS

#1: Packer set at 3199. TD 3219
open 30 min. weak blow for 9 min.
very slight SO BHP 40#

#2: Packer set at 3245 TD 3270
open 1 hr. fair blow rec. 270'
slightly oil cut salt water BHP 890#
15 min.

#3: Packer set at 3337 TD 3395 open
1 hr. fair blow rec. 445' salt water
BHP 240 # FFP 140# 15 min.