

Hammer No.

Form 113 50M 12-49-49234-D

State Kansas County Barton

Sec. 14 Twp. 19s Rng. 12w Elev. 1846

Company Aladdin

Well No. 3 Name Schartz

Location NE SE NW

Feet from lines: N. \_\_\_\_\_ S. \_\_\_\_\_ E. \_\_\_\_\_ W. \_\_\_\_\_

Spud 8-24-50 Completed 10-4-50

T. D. 3431 Casing 8" 242, 5" 3403.  
PBD 3386.

Comp. Perf. 3140-3209.

Pay \_\_\_\_\_

I. P. Phy Pot 346 BOPD plus 7% wtr.

Choke \_\_\_\_\_ T. P. \_\_\_\_\_ C. P. \_\_\_\_\_

**COMPLETION**

G. O. R. \_\_\_\_\_ Grvty. \_\_\_\_\_

| DATE              | REMARKS                          |
|-------------------|----------------------------------|
| 10-4-50           | Ann 670, L&V 3132, Arb 3400. DST |
| 3137-3210/15/350' | ocm. 1200 gassy oil.             |
| BHP 900#          | FP 350#. DST 3278-3320/60/60'    |
| 311 ocm.          | BHP 1360. RTD 3407. DPDD 3431.   |

DATE

REMARKS

18 GO 1 hr. 1000 ac. 2 1/2 BOPH3 hrs.  
 PB 3386. 21 1/2 3308-16. NS. 15 1/2 3303-08. NS.  
 21 1/2 3207-95. SSW. To sqz. 4 1/2 3198-3209.  
 700' Oil 15 min. 2000' Oil 2 1/2 hrs. 4 1/2  
 3176-90. 36 1/2 3154-64. 26 1/2 3143-52. 33 1/2  
 3129-40. 3000 ac. Phy Pot 346 BOPD plus  
 7% wtr.

COMPLETE.

620123