

28-19-19W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE CARL TODD DRILLING COMPANY
Farm- Seltman No. 1

SEC. 28 T. 19 R. 19W
SE SE SE

Total Depth. 4284
Comm. 4-11-53 Comp. 4-26-53
Shot or Treated.
Contractor.
Issued. 5-16-53

County Rush KANSAS



CASING:
8 5/8" 238' cem. w/150 sx

Elevation. 2273 RB
2271 (m)

Production. Dry

Figures indicate Bottom of Formations.

surface clay & rock	35	
gravel	50	
shale & shells	325	
sand & shale strks	375	
shale & shells	470	
sand & shale	525	
shale & shells	650	
red bed & shells	850	
sand	1025	
red bed & shells	1140	
anhydrite	1150	
red bed & shale	1600	
shale & shells	1970	
shale & lime	3417	
lime	3645	
lime & shale	3785	
lime	4065	
lime & shale	4161	
congl.	4181	
congl. & shale	4204	
arbuckle	4284	RTD
Total Depth		

Tops:

Heebner	3677
Lansing	3728
Base-Kansas City	4041
Marmaton	4063
Conglomerate	4152
Arbuckle	4204

DST: 4151-76' open 30 mins.
rec. 2725' salt wtr; BHP 1240#
in 15 mins.