

58  
✓

4-19-2W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- ALFRED KOEHN  
Farm- W.W. Johnson No. 1

SEC. 4 T. 19 R. 2W  
NE NW SE

Total Depth. 2980'  
Comm. 9-27-58. Comp. 10-3-58  
Shot or Treated.  
Contractor. J.A. Melland  
Issued. 1-24-59

County McPherson  
KANSAS



Elevation. 1563' RB

Production. 8 BOPD

CASING:

8 5/8" 187' w/120 sx cem.  
5 1/2" 2968 1/2' w/125 sx cem.

Figures indicate Bottom of Formations.

surface soil, clay, sand	160
shale, shells, sand	187
shale, shells	375
anhydrite, gypsum, lime	470
shale, shells	560
lime	850
shale, lime	1225
shale	1510
lime, shale	1570
shale, shells	1685
shale, lime	2130
sand, shale	2240
shale, lime	2353
lime	2435
lime, shale	2870
shale, lime	2963
Mississippi lime	2974 RTD
Mississippi lime	2980
Total Depth	

TOPS: SCOUT  
Mississippi 2965