


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. VAUGHN E. WIGGINS
Farm. Anderson No. 2

SEC. 18 T. 19 R. 2W
SE NW SW

Total Depth. 3018' PB 2375'
Comm. 7-28-60 Comp. 8-19-60
Shot or Treated.
Contractor. Glickman Oil Co.
Issued. 10-29-60

County McPherson
KANSAS



CASING:

10 3/4" 200' cem w/175 sx.
7" 2997 1/2' cem w/150 sx.

Elevation. 1542' RB

Production. 25 BOPD, tr wtr.

Figures Indicate Bottom of Formations.

sand, shale & shells	200
shale & shells	290
lime & shale	920
lime	1100
shale & lime	1825
lime & shale	2054
lime & shale	2395
lime	2638
lime & shale	2997
lime & shale	3000 RTD
chert	3018 CTTD
Total Depth	
Plugged back to 2375'	

TOPS:

Lansing-Kansas City 2334
Mississippi Chat 2997

Good show of oil from 2345 to 2358'
Show of oil 2997- to 3000'.

Mississippi acidized w/500 gals. & 1000
gals @ 3001'; recovered only light show
of oil & gas & light show of water.

Perforated from 2345' to 2353' w/32 shots

Acidized w/250 gals. & 1000 gals .