

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-19-2W

Company- FRANCIS O. HAWN ET AL
Farm- Salthouse No. 4

SEC. 15 T. 19 R. 2W
C N/2 N/2 SE/4

Total Depth. 3780'
Comm. 10-26-57 Comp. 11-10-57
Shot or Treated.
Contractor. E. K. Carey
Issued. 5-17-58

County McPherson
KANSAS



Elevation. 1567' KB

Production. S.W.D.W.

CASING:

8 5/8" 200' cem w/115 sx.
5 1/2" 3530' cem w/225 sx.

Figures indicate Bottom of Formations.

cellar & base	8
clay & shale	40
sandy shale	80
lime & shale	235
shale & lime	560
lime & shale	950
shale & lime	1675
lime & shale	1975
lime	2194
sand	2277
shale & lime	2337
lime	2625
lime & shale	2927
chat (Miss.)	3062
lime	3124
lime & shale	3184
shale & lime	3404
lime	3465
sand & lime	3506
lime (Arbuckle)	3780 RTD
Total Depth	

TOPS:

Kansas City	2324
Mississippi	2925
Kinderhook Shale	3124
Maquoketa Dolomite	3324
Sylvan Shale	3363
Viola	3404
Simpson	3442
Simpson Sand	3470
Arbuckle	3506

DST 3404-3409 or 5' anchor. Tool open 1 hr.
with fair blow. Closed 20 min. for BHP.
Rec. 70' heavy oil cut mud. BHP 540#.