



14-19-2W

Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

March 12, 1980

State Geological Survey
WICHITA BRANCH

COMPANY: CULVER - GROUNDS OIL PROPERTIES, INC.
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: EVANS #1 (Evans, A. 1 per KCC) KGS-
LOCATION: 660' NSL & 330' WEL SE SW 14-19-2W, GRI 002
McPherson County, Kansas
COMMENCED: March 5, 1980
COMPLETED: March 11, 1980
ELEVATION:

0	to	15	Dirt & Clay
15	to	60	Sand
60	to	350	Shale
350	to	650	Shale & Lime
650	to	890	Lime & Shale
890	to	1730	Shale & Lime
1730	to	2020	Lime & Shale
2020	to	2680	Shale & Lime
2680	to	2820	Lime & Shale
2820	to	2895	Shale & Lime
2895	to	2898	Lime & Shale
2898	to	3050	Mississippi
3050	to	3135	Mississippi & Shale
3135	to	3250	Shale
3250	to	3317	Shale & Lime
3317	to	3365	Shale
3365	to	3366	Viola
		3366	T. D.

Cut 17 1/2" hole to 133' and run 135' of 10 3/4" surface pipe, cemented with 115 sacks of cement at 133'. Plug down at 2:15 P. M., March 5, 1980. Drilled 8 3/4" hole to 3366'. Run 3374' of 7" casing, cemented at 3365', 1 foot off bottom with 125 sacks of cement. Plug down at 11:00 A. M., March 11, 1980.

TOPS: LANSING - 2301' MISSISSIPPI - 2898' KINDERHOOK - 3086' VIOLA - 3365

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Evans #1,
Kansas