


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

29-19-21W

Company- CITIES SERVICE OIL COMPANY  
Farm- Rein "B" No. 1

SEC. 29 T. 19 R. 21W  
C NW SE

County Ness  
KANSAS



Elevation. 2302' DF

Production. Dry

Total Depth. 4461'  
Comm. 5-24-64 Comp. 6-4-64  
Shot or Treated.  
Contractor. Peel Drilling Co.  
Issued. 8-22-64

CASING:

8 5/8" 531' cem w/300 sx.

Figures indicate Bottom of Formations.

surface clay & shale	130
shale	960
sand	1175
shale & redbed	1524
Anhydrite	1558
shale	1610
shale & shells	2400
lime	2905
lime & shale	2995
shale & lime	3110
lime & shale	3400
shale & lime	3470
lime	4452
chert	4461 RMD
Total Depth	

TOPS: ELEC. LOG

Heebner	3791
Toronto	3810
Lansing	3839
Fort Scott	4340
Cherokee	4357
Conglomerate	4412
Mississippian	4440

DST 4444-49' Op 1 hr. Rec. 35' oil cut  
mud. IBHP 1398#/30"; IFP 36#; FFP 45#;  
FBHP 1255#/30".

DST 4449-61' Op 1½ hrs. Rec. 3' oil &  
63' muddy oil & 126' sl. oil & gas cut  
mud & 252' salt wtr. IBHP 1365#/30";  
IFP 80#; FFP 208#; FBHP 1230#/30"