

CONTRACTOR'S WELL LOG

29-19-21W
15-035-21023

DRILLER:
CONTRACTOR:
WELL NAME:
LOCATION:

Cities Service Oil Company
Abercrombie Drilling, Inc.
REIN "A" #6
C SW NW Section 29-19S-21W
Ness County, Kansas

SPUD DATE:
COMPLETION DATE:

May 22, 1975
May 30, 1975

0	542	Clay & Shale
542	1547	Shale & Sand
1547	1570	Anhydrite
1570	1850	Shale & Lime
1850	2700	Shale
2700	4265	Shale & Lime
4265	4352	Lime & Shale
4352	4415	Shale & Lime
4415	4495	Lime
	4495	Rotary Total Depth

Drilled 542' of 12 1/4" surface hole, ran 14 jts. 8 5/8" surface casing, set @542'.
Cemented w/400 sx. 50/50 Posmix, 2% calcium chloride, cement circulated. Plug was down
50 p.m., May 21, 1975.

Plugged & Abandoned: 1st Plug Set @550' w/70 sx. cement; 2nd Plug Set @240' w/20 sx.
cement; 3rd Plug Set @40' w/10 sx. cement. Plug was down @8:00 a.m., May 30, 1975.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)


Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc. does hereby
state that the above and foregoing is a true and correct copy of the log of ~~the~~ REIN
#6, C SW NW Section 29-19S-21W, Ness County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
Jerry A. Langrehr-Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county
and state as of this 4th day of June, 1975.

Nancy E. Haner
Nancy E. Haner-Notary Public



Commission Expires: April 8, 1978