

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


Company- Cities Service Oil Co.  
Farm- Moore "B" No. 3

SEC. 30 T. 19 R.21W  
C NE SE

Total Depth. 4467'  
Comm. 8-17-64 Comp. 8-30-64  
Shot or Treated.  
Contractor. Peel Brothers  
Issued. 11-7-64

County NESS

KANSAS



Elevation. 2301 KB

Production. D & A

Figures Indicate Bottom of Formations.

Surface clay & shale	160
Shale & Shells	960
Sand	1195
Shale	1522
Anhydrite	1555
Shale & Shells	2280
Lime & Shale	2510
Lime	2765
Lime & Shale	2880
Shale & Lime	3045
Lime & Shale	3635
Lime, Chalk, & Shale	3745
Lime	4416
Lime & Chert	4467
TOTAL DEPTH	

Elec. Log Tops:

Heebmer	3789
Toronto	3807
Lansing	3827
Base Kansas City	4159
Fort Scott	4335
Cherokee	4354
Conglomerate	4401
Mississippian	4424

D.S.T. 4426-32'. Op. 1/2 hr. Rec. 15'  
mud w/a few oil spks. I.B.H.P. 280#/30", I.F.P. 9#, F.F.P. 9#, F.B.H.P. 99#/30".

D.S.T. 4432-39'. Op. 1 hr. Rec. 60'  
oily mud. I.B.H.P. 1301#/30", I.F.P. 5#, F.F.P. 36#, F.B.H.P. 1182#/30".

D.S.T. 4439-47'. Op. 1 1/2 hr. Rec. 15' sli.  
Muddy oil, 90' heavily oil cut mud &  
30' muddy salt water. I.B.H.P. 1327#/30".  
I.F.P. 9#, F.F.P. 13#, F.B.H.P. 1239#/30".