

30-19-21W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.  
Farm- Moore "B" No. 4

SEC. 30 T. 19 R. 21W  
CW/2 NW NE  
660' S & 2130' W of  
Ne cor.

Total Depth. 4428'  
Comm. 4-15-65 Comp. 4-25-65  
Shot or Treated.  
Contractor. Peel Bros., Inc.  
Issued. 7-31-65

County Ness  
KANSAS



Elevation. 2294' D.F.

Production. 121 BO, NWPD

CASING:

8 5/8" 506' w/275 sx cem.  
4 1/2" 4426' w/100 sx cem.

Figures Indicate Bottom of Formations.

shale, shells	875
shale	948
sand	1180
shale, shells	1507
anhydrite	1540
shale, shells	2255
shale, lime	2283
lime, shale	2660
lime	2770
lime, shale	3790
lime	4096
lime, shale	4185
lime	4427 RTD
lime	4428
Total Depth	

TOPS:	ELEC.
Heebner Elec.	3761
Lansing "	3811
Fort S ott	4305
Conglomerate	4370
Mississippian	4393

TOPS: SCOUT	
Anhydrite	1507
Toronto	3777
B/Kansas City	4132
Cherokee	4322

PERF: 4408-14' w/ 18 shots.  
ACID 250 gals.