

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- **CITIES SERVICE OIL**
 Farm- **Moore "B" No. 5**

SEC. 30 T. 19 R. 21W
C SW NE
1874' FNL & 2086' FEL

Total Depth. **4408 P.B.T.D. 4404**
 Comm. **6-18-65** Comp. **6-28-65**
 Shot or Treated. **1**
 Contractor. **Peel Bros., Inc.**
 Issued. **3-12-66**

County **Ness**

KANSAS



Elevation. 2278' KB

Production. **123 BOPD, NO WTR.**

Figures Indicate Bottom of Formations.

CASING:

3 5/8" @ 520' w/275 sx.
 4 1/2" @ 4404' w/100 sx.

clay & shale	435
shale & shells	520
shale	935
sand	1150
red bed & shale	1490
red bed	1495
anhydrite	1533
shale & shells	1800
shale	2190
shale & lime	2275
lime & shale	2561
lime	2752
lime & shale	3765
lime	4385
cherty lime	4395
lime	4405 RTD
Total Depth	

SCHLUMBERGER LOG TOPS:

Anhydrite	1495
Heebner	3759
Toronto	3776
Lansing	3808
Base Kansas City	4129
Pawnee	4227
Fort Scott	4303
Cherokee	4321
Warsaw	4386
Osage	4388
Log Total Depth	4408
Pen. Mississippi	20'

P.B.T.D. 4404. Perf 12 shots 4388-92. Rec. load wtr., swb 5 gal oil P.HP for 2 hrs. Az w/250 gal. 7 1/2 C.A. acid. Swb 27.9 B. O. & 1 B.W./4 hrs.