

30-19-21W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL  
Farm Moore "D" No. 2

SEC. 30 T. 19 R21W  
150' SW/c NW NW  
766' S & 554' E. of NW corner


Total Depth. 4400' P.B.T.D. 4397'

County Ness

Comm. 2-2-65 Comp. 3-6-65

KANSAS

Shot or Treated. Mississippian, 4384-4390', 250 Gass. acid, 18 shots



Contractor. Peel Bros.

Issued. 5-22-65

CASING:

8 5/8" 510' w/275 sx.  
4 1/2" 4399' w/ 100 sx.

Elevation. 2270' KB

Production. 153 BO, tr. wtr./24 hrs.

Figures Indicate Bottom of Formations.

surface clay & shale	75
postrick & shale	110
shale	155
shale & shells	914
sand	1165
sand, shale & shells	1227
shale & red beds	1484
anhydrite	1516
shale	1572
shale & shells	2400
shale & lime	2580
lime & shale	2675
shale & lime	2780
lime & shale	3095
shale & lime	3270
lime & shale	3425
shale & lime	3555
lime & shale	3705
shale, lime & pyrite	3795
lime	3850
lime & shale	3890
lime	4245
lime & shale	4315
lime & conglomerate	4359
Mississippi	4388
lime & chert	4400
RTD	

ELECTRIC LOG TOPS:

Heebner	3733
Lansing	3783
Base Kansas City	4107
Fort Scott	4280
Cherokee	4297
Conglomerate	4342
Mississippi (Warsaw)	4366
Osage	4377
Log TD	4398