

15-135-24552

23-19s-21w

SCOTT CORSAIR

PETROLEUM GEOLOGIST #55

210 W Avenue A P.O. Box 6
Bazine, Ks 67516
785-398-2270 Mobile 785-731-5060
FAX 785-398-2586

GEOLOGICAL REPORT

AMERICAN WARRIOR, INC.

Antenen #2-23
2330' FSL & 1915' FEL
Section 23-19S-21W
Ness County, KS
API# 15-135-24552

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 21 2007

CONSERVATION DIVISION
WICHITA, KS

OPERATOR: AMERICAN WARRIOR, INC.

WELL: ANTENEN #2-23

API NO.: 15-135-24552

LOCATION: 1810' FNL & 365' FEL, 23-19S-21W, NESS COUNTY, KANSAS

WELLSITE: PASTURE

COMMENCED: OCTOBER 26, 2006

COMPLETED: NOVEMBER 2, 2006

ELEVATIONS: 2277' GL ; 2283' KB

TOTAL DEPTH: 4460' (DRILLER); 4465' (LOG)

CASING: SURFACE: 8 5/8 @ 211' W/ 160 SKS.

SAMPLES: 10 FT. FROM 3600' TO T.D.

LOGS: DUAL INDUCTION, DUAL COMPENSATED POROSITY, (LOG-TECH)

DRILLSTEM TESTS: NONE

CONTRACTOR: PETROMARK (RIG #1)

REMARKS: Geological supervision: 3600' - T.D.

FORMATION TOPS	ELECTRICAL LOG SUBSEA		SAMPLES SUBSEA	
Anhydrite	1512	+771	1513	+770
Chase	2420	-130		
Heebner	3792	-1509	3788	-1505
Lansing	3838	-1555	3835	-1552
Base KC	4156	-1873	4154	-1871
Pawnee	4280	-1997	4274	-1991
Ft. Scott	4311	-2028	4308	-2025
Cherokee	4326	-2043	4322	-2039
Mississippian	4411	-2128	4407	-2124
Total Depth	4465	-2182	4460	-2177

SAMPLE ZONE DESCRIPTION

Logger's Measurements

LANSING-KANSAS CITY 3838 -1555

There were no shows of oil/gas observed in the porous zones during the drilling of the Lansing-Kansas City section.

FT. SCOTT 4311 -2028

There were no shows of oil/gas observed in the porous zones during the drilling of the Ft. Scott section.

CHEROKEE 4326 -2043

There were no shows of oil/gas observed in the porous zones during the drilling of the Cherokee section.

MISSISSIPPIAN 4411 -2128

Chert: white& tan, fresh, angular, no visible porosity, no visible show, no fluorescence or cut, barren. No gas kick. Trace of **Dolomite:** tan & gray, sucrosic, barren.


FORMATION	American Warrior Antenen #2-23 1810' FNL & 365' FEL; 23-19S-21W Ness County, KS	American Warrior Antenen #1-23 2330' FSL & 1915' FEL; 23-19S-21W Ness County, KS	Leben #1 Antenen C NW SE; 23-19S- 21W, Ness County, KS
Anhydrite	+771	+773	+772
Heebner	-1509	-1500	-1499
Lansing	-1555	-1544	-1543
Ft. Scott	-2028	-2019	-2024
Mississippian	-2128	-2121	-2115


SUMMARY AND RECOMMENDATIONS

Structural position, gas detector results, sample examination and Electrical log analysis prove this test as non-commercial. This well was plugged and abandoned on November 02, 2006.

Measurements were taken from rotary kelly bushing (6 feet above ground level). Log measurements are taken as correct.

Respectfully


Scott Corsair
Petroleum Geologist #55



5-15-07