

16-19-21W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WALTERS DRIG. CO. & FERGUSON OIL CO.
Farm- Wilhelm No. 1

SEC. 16 T. 19 R. 21W
C NW SE

Total Depth. 4400'
Comm. 2-6-64 Comp. 2-18-64
Shot or Treated.
Contractor. Walters Drig. Co.
Issued. 4-17-65

County Ness
KANSAS



CASING:

Elevation. 2257 D.F.

8 5/8" 495' w/250 sx cem.

Production. DRY

Figures Indicate Bottom of Formations.

surface sand	20
sand w/shale	170
shale	380
sand	450
shale	625
shale, red bed	910
sand, shale	1220
shale	1410
red bed	1460
Anhydrite	1496
shale	2270
shale, lime	2435
lime, shale	3370
shale, lime	3490
lime, shale	3660
lime	3740
lime, shale	3800
lime	4140
lime, shale	4185
lime	4305
lime, shale	4325
lime	4380
lime, chert	4385
lime	4400
Rotary Total Depth	

TOPS: SCOUT	
Stone Corral	1462-96
Heebner	3741
Lansing	3786
B/Kansas City	4086
Marmaton	4120
Pawnee	4196
Fort Scott	4269
Cherokee shale	4283
Mississippi Warsaw	4357
Mississippi Osage	4370