

WICHITA BRANCH
KANSAS DRILLERS LOG

15-135-21402


API No. 15 — 135 — 21,402
County Number

S. 17 T. 19S R. 21W

Loc. NE SW SE

County Ness

640 Acres
N



Locate well correctly

Elev.: Gr. 2,250'

DF _____ KB 2,255'

Operator: ICER ADDIS

Address: Drawer 8038, Wichita, Kansas 67208

Well No. 1 Lease Name MARGHEIM

Footage Location: feet from (N) (S) line _____ feet from (E) (W) line _____

Principal Contractor: Strata Drilling Company Geologist: Richard M. Foley

Spud Date: December 30, 1977 Total Depth: 4,360' P.B.T.D. _____

Date Completed: January 6, 1978 Oil Purchaser: Getty Oil Company

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	28#	283'	Common	190	2% Gel, 3% CaCh
Production	7-7/8"	5-1/2"	14#	4,355'	60-40 Pozmix	125	18% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at
2-7/8" OD	4,357'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production: February 7, 1978 Producing method (flowing, pumping, gas lift, etc.): Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil 25 bbls.	Gas _____ MCF	Water Trace bbls.	Gas-oil ratio _____ CFPB
---------------------------------	--------------	---------------	-------------------	--------------------------

Disposition of gas (vented, used on lease or sold): _____ Producing interval(s): Mississippi Osage

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Operator ICER ADDIS

Well No. 1 Lease Name MARGHEIM OIL

S 17 T 19S R 21 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	1,462			
Heebner	3,720			
Toronto	3,740			
Lansing	3,767			
Pawnee	4,182			
Ft. Scott	4,255			
Cherokee	4,270			
Cherokee Lime	4,306			
Conglomerate	4,339			
Mississippi Osage	4,353			
RTD	4,360			
DST #1: Open 60" (30-30-30-30) Strong blow. Recovered 2,000' gas, 190' oil, slightly muddy. ISIP 913#, FSIP 825#, IFP 40-64#, FFP 81-105#.	4,259	4,270		
DST #2: Open 60" (30-30-30-30) Very weak blow. Recovered 25' mud. ISIP 503#, FSIP 332#, IRP 18-18#, FFP 18-24#	4,269	4,285		
DST #3: Open 60" (30-30-30-30) Strong blow. Recovered 540' gas, 745' clean gassy oil, 375' muddy oil (Total fluid 1,120'). ISIP 1,232#, FSIP 1,211#, IFP 43-212#, FFP 212-372#	4,355	4,360		
Completed, Open Hole in Mississippi Osage				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Icer Addis Signature
 Owner-Operator Title
 February 15, 1978 Date