


15-135-24509

33-19S-21W



DRILL STEM TEST REPORT

Prepared For: **American Warrior Inc**

PO Box 399
Garden City KS 67849

ATTN: Scott Corsair

33 19S 21W Ness KS

Schwartz-Jordan #1

Start Date: 2006.08.25 @ 18:43:09

End Date: 2006.08.26 @ 05:40:34

Job Ticket #: 26201 DST #: 1

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

American Warrior Inc

PO Box 399
Garden City KS 67849

ATTN: Scott Corsair

Schwartz-Jordan #1

33 19S 21W Ness KS

Job Ticket: 26201

DST#: 1

Test Start: 2006.08.25 @ 18:43:09

GENERAL INFORMATION:

Formation: **Mississippian**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 00:19:33

Time Test Ended: 05:40:34

Test Type: **Conventional Bottom Hole**

Tester: **Tyson Flax**

Unit No: **21**

Interval: **4425.00 ft (KB) To 4435.00 ft (KB) (TVD)**

Total Depth: **4435.00 ft (KB) (TVD)**

Hole Diameter: **7.88 inches** Hole Condition: **Good**

Reference Elevations: **2291.00 ft (KB)**

2286.00 ft (CF)

KB to GR/CF: **5.00 ft**

Serial #: 8289

Inside

Press@RunDepth: **91.21 psig @ 4426.00 ft (KB)**

Start Date: **2006.08.25**

End Date:

2006.08.26

Start Time: **18:43:09**

End Time:

05:40:34


Capacity: **7000.00 psig**

Last Calib.: **2006.08.26**

Time On Btm: **2006.08.26 @ 00:19:03**

Time Off Btm: **2006.08.26 @ 02:19:33**

TEST COMMENT: **IFP BOB in 30 min**
ISI Weak surface blow back throughout
FFP BOB in 27 min
FSI Weak surface blow back



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2210.80	114.36	Initial Hydro-static
1	16.63	113.51	Open To Flow (1)
32	51.31	119.39	Shut-In(1)
60	1333.48	121.52	End Shut-In(1)
60	53.54	121.10	Open To Flow(2)
92	91.21	122.82	Shut-In(2)
120	1313.64	123.56	End Shut-In(2)
121	1991.94	123.79	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
145.00	CO 100%O	2.03
60.00	VSOCMW 5%O 30%M 65%W	0.84

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior Inc

Schwartz-Jordan #1

PO Box 399
Garden City KS 67849

33 19S 21W Ness KS

Job Ticket: 26201

DST#: 1

ATTN: Scott Corsair

Test Start: 2006.08.25 @ 18:43:09

Tool Information

Drill Pipe:	Length: 4413.00 ft	Diameter: 3.80 inches	Volume: 61.90 bbl	Tool Weight: 2500.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose: lb
			<u>Total Volume: 61.90 bbl</u>	Tool Chased ft
Drill Pipe Above KB:	16.00 ft			String Weight: Initial 54000.00 lb
Depth to Top Packer:	4425.00 ft			Final lb
Depth to Bottom Packer:	ft			
Interval between Packers:	10.00 ft			
Tool Length:	38.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		
Tool Comments:				

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			4398.00	
Shut In Tool	5.00			4403.00	
Hydraulic tool	5.00			4408.00	
Jars	5.00			4413.00	
Safety Joint	2.00			4415.00	
Packer	5.00			4420.00	28.00 Bottom Of Top Packer
Packer	5.00			4425.00	
Stubb	1.00			4426.00	
Recorder	0.00	8289	Inside	4426.00	
Perforations	6.00			4432.00	
Recorder	0.00	13409	Inside	4432.00	
Bullnose	3.00			4435.00	10.00 Bottom Packers & Anchor

Total Tool Length: 38.00



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior Inc

Schwartz-Jordan #1

PO Box 399
Garden City KS 67849

33 19S 21W Ness KS

Job Ticket: 26201

DST#: 1

ATTN: Scott Corsair

Test Start: 2006.08.25 @ 18:43:09

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 48.00 sec/qt

Cushion Volume:

bbl

Water Loss: 9.56 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 7500.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
145.00	CO 100%O	2.034
60.00	VSOCMW 5%O 30%M 65%W	0.842

Total Length: 205.00 ft

Total Volume: 2.876 bbl

Num Fluid Samples: 0


Num Gas Bombs: 0


Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:





TRILOBITE TESTING INC.

P.O. Box 362 • Hays, Kansas 67601

26201

9177

Test Ticket

Well Name & No. Schwartz - Jordan #1 Test No. 1 Date 8/25/06
 Company American Warrior, Inc. Zone Tested Mississippian
 Address P.O. Box 399 Garden City, KS 67846 Elevation 2291 KB 2286 GL
 Co. Rep / Geo. Scott Corsair Rig Petromark #1
 Location: Sec. 33 Twp. 19S Rge. 21W Co. Ness State KS
 Comment: _____ Release date / time: _____

Interval Tested 4425-4435 Initial Str Wt./Lbs. 52000 Unseated Str Wt./Lbs. 52000
 Anchor Length 10' Wt. Set Lbs. 25000 Wt. Pulled Loose/Lbs. 60000
 Top Packer Depth 4420 Tool Weight 2500
 Bottom Packer Depth 4425 Hole Size 7 7/8" Rubber Size 6 3/4"
 Total Depth 4435 Wt. Pipe Run _____ Drill Collar Run _____
 Mud Wt. 9.4 LCM _____ Vis. 48 WL 9.6 Drill Pipe Size 4 1/2 X H Ft. Run 4413
 Blow Description IFD - BOB in 30 min

ISI - weak surface blow back throughout

FFP - BOB in 27 min

FSI - weak surface blow back throughout

Recovery - Total Feet 205 GIP _____ Ft. in DC _____ Ft. in DP 205
 Rec. 145 Feet of CO %gas 100 %oil _____ %water _____ %mud _____
 Rec. 60 Feet of VSOC MW %gas 5 %oil 65 %water 30 %mud _____
 Rec. _____ Feet of _____ %gas _____ %oil _____ %water _____ %mud _____
 Rec. _____ Feet of _____ %gas _____ %oil _____ %water _____ %mud _____
 Rec. _____ Feet of _____ %gas _____ %oil _____ %water _____ %mud _____
 BHT 124 °F Gravity 43 °API D @ 63 °F Corrected Gravity 43 °API
 RW _____ @ _____ °F Chlorides _____ ppm Recovery _____ Chlorides 7500 ppm System

(A) Initial Hydrostatic Mud	AK-1	Alpine	Recorder No.	8289	Test x	1200
(B) First Initial Flow Pressure	2219	PSI	(depth)	4426	Jars x	250
(C) First Final Flow Pressure	17	PSI	Recorder No.	13409	Safety Jt. x	75
(D) Initial Shut-In Pressure	51	PSI	(depth)	4432	Circ Sub	
(E) Second Initial Flow Pressure	1333	PSI	Recorder No.		Sampler	
(F) Second Final Flow Pressure	54	PSI	(depth)		Straddle	
(G) Final Shut-In Pressure	91	PSI	Initial Opening	30	Ext. Packer	
(Q) Final Hydrostatic Mud	1314	PSI	Initial Shut-In	30	Shale Packer	
	2103	PSI	Final Flow	30	Ruined Packer	
			Final Shut-In	30	Mileage x 10¢	132.50
			T-On Location	18:16	Sub Total:	1657.50
			T-Started	18:45	Std. By 2.25	325.00
			T-Open	60:21	Acc. Chg:	
			T-Pulled	02:21	Other:	
			T-Out	05:30	Total:	\$1882.50

TRILOBITE TESTING INC. SHALL NOT BE LIABLE FOR DAMAGED OF ANY KIND OF THE PROPERTY OR PERSONNEL OF THE ONE FOR WHOM A TEST IS MADE, OR FOR ANY LOSS SUFFERED OR SUSTAINED, DIRECTLY OR INDIRECTLY, THROUGH THE USE OF ITS EQUIPMENT, OR ITS STATEMENTS OR OPINION CONCERNING THE RESULTS OF ANY TEST. TOOLS LOST OR DAMAGED IN THE HOLE SHALL BE PAID FOR AT COST BY THE PARTY FOR WHOM THE TEST IS MADE.

Approved By _____
 Our Representative By FHP

CHART PAGE

This is a photocopy of the actual AK-1 recorder chart.

An Warior
Schwarz-Eden
DST #1

