

PALOMINO PETROLEUM

304 INSURANCE BUILDING
WICHITA, KANSAS 67202

R. W. WATCHOUS
OWNER - GEOLOGIST

(316) 263-4961

PROGRESS REPORT

Palomino Petroleum
#1 Margheim "C"
NW NE SE Sec. 17-19S-21W
Ness County, Kansas

Elevation: 2225 R.B. (Corrected from 2226')

10-14-76 Moved in rotary tools and spudded.
Set 28# used seamless 8 5/8" surface casing at 307'
and cemented with 190 sacks (circulated).
Plug down at 9:00 p.m.

10-15-76 Drilling @ 315'.

10-16-76 Top Cim. Anhydrite 1432 (+793) to 1466
Drilling @ 2200'.

10-18-76 Drilling @ 3440'.

10-19-76 Drilling @ 4080' @ 7:00 a.m.

10-20-76 Top Heebner 3693 (-1468)
Top Lansing 3737 (-1512)
Top Ft. Scott 4232 (-2007)
Fair show of oil in Ft. Scott.
Upper Cherokee Sand 4251 (-2026)

D.S.T. #1 4218-4254 30-30-30-45" Recovered 290' fluid;
20' oily, watery mud, 270' muddy water. Flow Pressures
101# to 182#. SIP 806# to 826#.

Going back into the hole.

Thursday 10-21-76 Mississippian-Warsaw 4324 (-2099)
Very small show of oil approximately 4340-4362
Mississippian-Osage 4362 (-2137)
Very small show of oil 4362
Rotary Total Depth 4365 (Quite Low)
D.S.T. #2 4338-4365 Open 1 hour, weak blow for 42 minutes
(flushed tool twice), recovered 60' very slightly oil cut
mud. 30 minute SIP 1005#. Flow Pressures 81# to 81#.

Running open hole electric log to double check Cherokee
section (no lower sand found in samples).

Best Scanned Copy

PROGRESS REPORT

#1 Margheim "C"

Page 2

Electric Log Tops:

Heebner	3695	(-1470)
Lansing-KC	3739	(-1514)
Ft. Scott	4235	(-2010)
Upper Cherokee Sand	4254	(-2029)
Cherty Conglomerate	4305	(-2080)
Mississippian Warsaw	4325	(-2100)
Mississippian Osage	Not logged--Log TD 4362 (6' off bottom)	

Dry and Abandoned.