26-19S-22W
NW SE NW SW

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **American Warrior Inc.**

Box 399
Garden City KS

ATTN: Scott Corsair

26-19s 22w Ness KS

Shank 1-26

Start Date: 2005.09.17 @ 22:22:16
End Date: 2005.09.18 @ 04:56:16
Job Ticket #: 22150 DST #: 1

15-135-24382-00-00

RECEIVED
MAR 3 1 2006
KCC WICHITA

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

DRILL STEM TEST REPORT

TRILOBITE TESTING, INC

American Warrior Inc.

Box 399
Garden City KS

ATTN: Scott Corsair

Shank 1-26

26-19s 22w Ness KS

Job Ticket: 22150 **DST#: 1**

Test Start: 2005.09.17 @ 22:22:16

GENERAL INFORMATION:

Formation: **Mississippian**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 01:09:16
Time Test Ended: 04:56:16

Test Type: Conventional Bottom Hole
Tester: Paul Simpson
Unit No:


Interval: 4330.00 ft (KB) To 4384.00 ft (KB) (TVD)
Total Depth: 4384.00 ft (KB) (TVD)
Hole Diameter: 7.88 inches Hole Condition: Good

Reference Elevations: 2257.00 ft (KB)
2249.00 ft (CF)
KB to GR/CF: 8.00 ft

Serial #: 8018 **Inside**
Press@RunDepth: 39.23 psig @ 4334.00 ft (KB)
Start Date: 2005.09.17 End Date: 2005.09.18
Start Time: 22:22:21 End Time: 04:56:15

Capacity: 7000.00 psig
Last Calib.: 2004.12.18
Time On Btm: 2005.09.18 @ 01:08:16
Time Off Btm: 2005.09.18 @ 02:22:46

TEST COMMENT: IF- weak .25" blow decreasing to surface
FF-no blow



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2128.41	112.02	Initial Hydro-static
1	42.28	111.49	Open To Flow (1)
33	39.23	112.15	Shut-In(1)
61	101.72	112.87	End Shut-In(1)
62	34.71	112.82	Open To Flow (2)
74	38.51	113.08	Shut-In(2)
75	2026.27	113.70	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
5.00	mud	0.07

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior Inc.

Box 399
Garden City KS

ATTN: Scott Corsair

Shank 1-26

26-19s 22w Ness KS

Job Ticket: 22150 **DST#: 1**

Test Start: 2005.09.17 @ 22:22:16

Tool Information

Drill Pipe:	Length:	4316.00 ft	Diameter:	3.80 inches	Volume:	60.54 bbl	
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	
Drill Collar:	Length:	0.00 ft	Diameter:	2.25 inches	Volume:	0.00 bbl	
					Total Volume:	60.54 bbl	

Drill Pipe Above KB:	14.00 ft
Depth to Top Packer:	4330.00 ft
Depth to Bottom Packer:	ft
Interval betw een Packers:	49.00 ft
Tool Length:	77.00 ft
Number of Packers:	2 Diameter: 6.75 inches

Tool Weight:		2500.00 lb
Weight set on Packer:		20000.00 lb
Weight to Pull Loose:		80000.00 lb
Tool Chased		ft
String Weight:	Initial	64000.00 lb
	Final	64000.00 lb

Tool Comments:
Send Copies of Ness County tests to Scott at Bazine

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths	
Change Over Sub	1.00			4303.00		
Shut In Tool	5.00			4308.00		
Hydraulic tool	5.00			4313.00		
Jars	5.00			4318.00		
Safety Joint	3.00			4321.00		
Packer	4.00			4325.00	28.00	Bottom Of Top Packer
Packer	5.00			4330.00		
Stubb	1.00			4331.00		
Perforations	2.00			4333.00		
Change Over Sub	1.00			4334.00		
Recorder	0.00	8018	Inside	4334.00		
Blank Spacing	31.00			4365.00		
Change Over Sub	1.00			4366.00		
Recorder	0.00	11084	Outside	4366.00		
Perforations	10.00			4376.00		
Bullnose	3.00			4379.00	49.00	Bottom Packers & Anchor
Total Tool Length:	**77.00**					

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior Inc.

Box 399
Garden City KS

ATTN: Scott Corsair

Shank 1-26

26-19s 22w Ness KS

Job Ticket: 22150 **DST#: 1**

Test Start: 2005.09.17 @ 22:22:16

Mud and Cushion Information

Mud Type:	Gel Chem	Cushion Type:		Oil API:	deg API
Mud Weight:	9.00 lb/gal	Cushion Length:	ft	Water Salinity:	ppm
Viscosity:	55.00 sec/qt	Cushion Volume:	bbl		
Water Loss:	10.18 in³	Gas Cushion Type:			
Resistivity:	ohm.m	Gas Cushion Pressure:	psig		
Salinity:	ppm				
Filter Cake:	inches				


Recovery Information

Recovery Table

Length ft	Description	Volume bbl
5.00	mud	0.070

Total Length: 5.00 ft Total Volume: 0.070 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #:
Laboratory Name: Laboratory Location:
Recovery Comments:


Pressure vs. Time
8018 Pressure
8018 Temperature
Initial Hydro-static
Final Hydro-static
Open To Flow(1)
Shut-In(1)
End Shut-In(1)
Open To Flow(2)
Shut-In(2)
Pressure
Temperature
2250
2000
1750
1500
1250
1000
750
500
250
0
115
110
105
100
95
90
85
80
75
70
18 Sun
3AM
Time (Hours)
Sep 2005



TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **American Warrior Inc.**

Box 399
Garden City KS

ATTN: Scott Corsair

26-19s 22w Ness KS

Shank 1-26

Start Date: 2005.09.17 @ 22:22:16
End Date:
Job Ticket #: 22251 DST #: 2

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

DRILL STEM TEST REPORT

TRILOBITE TESTING, INC

American Warrior Inc.

Box 399
Garden City KS

ATTN: Scott Corsair

Shank 1-26

26-19s 22w Ness KS

Job Ticket: 22251 **DST#: 2**

Test Start: 2005.09.17 @ 22:22:16

GENERAL INFORMATION:

Formation: **Mississippian**
Deviated: No Whipstock: ft (KB)
Time Tool Opened:
Time Test Ended:

Test Type: Conventional Bottom Hole
Tester: Paul Simpson
Unit No: 32


Interval: 4335.00 ft (KB) To 4397.00 ft (KB) (TVD)
Total Depth: 4397.00 ft (KB) (TVD)
Hole Diameter: 7.88 inches Hole Condition: Good

Reference Elevations: 2257.00 ft (KB)
2249.00 ft (CF)
KB to GR/CF: 8.00 ft

Serial #: 8018 **Inside**
Press@RunDepth: psig @ 4339.00 ft (KB)
Start Date: 2005.09.18 End Date: 2005.09.18
Start Time: 14:30:19 End Time: 19:11:43

Capacity: 7000.00 psig
Last Calib.: 2004.12.18
Time On Btm: 2005.09.18 @ 16:56:44
Time Off Btm: 2005.09.18 @ 16:57:44

TEST COMMENT: Packer Failure



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2106.67	108.20	Initial Hydro-static
1	926.64	107.90	Open To Flow (1)
1	2068.89	109.52	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
180.00	mud	2.52

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior Inc.

Box 399
Garden City KS

ATTN: Scott Corsair

Shank 1-26

26-19s 22w Ness KS

Job Ticket: 22251 **DST#: 2**

Test Start: 2005.09.17 @ 22:22:16

Tool Information

Drill Pipe:	Length:	4318.00 ft	Diameter:	3.80 inches	Volume:	60.57 bbl	Tool Weight:	2500.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	Weight set on Packer:	30000.00 lb
Drill Collar:	Length:	0.00 ft	Diameter:	2.25 inches	Volume:	0.00 bbl	Weight to Pull Loose:	66000.00 lb
					Total Volume:	60.57 bbl	Tool Chased	ft
Drill Pipe Above KB:		11.00 ft					String Weight: Initial	64000.00 lb
Depth to Top Packer:		4335.00 ft					Final	64000.00 lb
Depth to Bottom Packer:		ft						
Interval between Packers:		57.00 ft						
Tool Length:		85.00 ft						
Number of Packers:		2	Diameter:	6.75 inches				

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths	
Change Over Sub	1.00			4308.00		
Shut In Tool	5.00			4313.00		
Hydraulic tool	5.00			4318.00		
Jars	5.00			4323.00		
Safety Joint	3.00			4326.00		
Packer	4.00			4330.00	28.00	Bottom Of Top Packer
Packer	5.00			4335.00		
Stubb	1.00			4336.00		
Perforations	2.00			4338.00		
Change Over Sub	1.00			4339.00		
Recorder	0.00	8018	Inside	4339.00		
Blank Spacing	31.00			4370.00		
Change Over Sub	1.00			4371.00		
Recorder	0.00	11084	Outside	4371.00		
Perforations	18.00			4389.00		
Bullnose	3.00			4392.00	57.00	Bottom Packers & Anchor
Total Tool Length:	**85.00**					

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior Inc.

Box 399
Garden City KS

ATTN: Scott Corsair

Shank 1-26

26-19s 22w Ness KS

Job Ticket: 22251 **DST#: 2**

Test Start: 2005.09.17 @ 22:22:16

Mud and Cushion Information

Mud Type:	Gel Chem	Cushion Type:		Oil API:	deg API
Mud Weight:	9.00 lb/gal	Cushion Length:	ft	Water Salinity:	ppm
Viscosity:	55.00 sec/qt	Cushion Volume:	bbl		
Water Loss:	10.17 in³	Gas Cushion Type:			
Resistivity:	ohm.m	Gas Cushion Pressure:	psig		
Salinity:	ppm				
Filter Cake:	inches				


Recovery Information

Recovery Table

Length ft	Description	Volume bbl
180.00	mud	2.525

Total Length: 180.00 ft Total Volume: 2.525 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #:
Laboratory Name: Laboratory Location:
Recovery Comments:


Pressure vs. Time
8018 Pressure
8018 Temperature
Final Hydro-static
Initial Hydro-static
Open To Flow(1)
Pressure
Temperature
2250
2000
1750
1500
1250
1000
750
500
250
0
110
105
100
95
90
85
80
75
3PM
4PM
5PM
6PM
7PM
Time (Hours)
18 Sun Sep 2005



TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **American Warrior Inc.**

Box 399
Garden City KS

ATTN: Scott Corsair

26-19s 22w Ness KS

Shank 1-26

Start Date: 2005.09.19 @ 02:46:01
End Date: 2005.09.19 @ 11:50:01
Job Ticket #: 22252 DST #: 3

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

DRILL STEM TEST REPORT

TRILOBITE TESTING, INC

American Warrior Inc.

Box 399
Garden City KS

ATTN: Scott Corsair

Shank 1-26

26-19s 22w Ness KS

Job Ticket: 22252 **DST#: 3**

Test Start: 2005.09.19 @ 02:46:01

GENERAL INFORMATION:

Formation: **Mississippian**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 05:31:01
Time Test Ended: 11:50:01

Test Type: Conventional Bottom Hole
Tester: Paul Simpson
Unit No: 32

Interval: 4297.00 ft (KB) To 4397.00 ft (KB) (TVD)
Total Depth: 4397.00 ft (KB) (TVD)
Hole Diameter: 7.88 inches Hole Condition: Good


Reference Elevations: 2257.00 ft (KB)
2249.00 ft (CF)
KB to GR/CF: 8.00 ft

Serial #: 8018 **Inside**

Press@RunDepth: 133.40 psig @ 4301.00 ft (KB)
Start Date: 2005.09.19 End Date: 2005.09.19
Start Time: 02:46:06 End Time: 11:50:01

Capacity: 7000.00 psig
Last Calib.: 2005.09.19
Time On Btm: 2005.09.19 @ 05:30:01
Time Off Btm: 2005.09.19 @ 09:15:01

TEST COMMENT: IF- 1" blow building to 9.5"
ISI no blow
FF- Surface blow building to 9.5"
FSI- surface blow



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2101.27	114.80	Initial Hydro-static
1	26.96	114.67	Open To Flow (1)
32	72.42	118.55	Shut-In(1)
61	1288.94	119.16	End Shut-In(1)
62	76.57	118.60	Open To Flow (2)
106	133.40	119.39	Shut-In(2)
225	1320.51	120.21	End Shut-In(2)
225	2035.61	120.40	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
230.00	GOCM-5%G-40%O-55%M	3.23
50.00	Gassy oil 5%G-95%O	0.70
0.00	60 Gas in pipe	0.00

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior Inc.

Box 399
Garden City KS

ATTN: Scott Corsair

Shank 1-26

26-19s 22w Ness KS

Job Ticket: 22252 **DST#: 3**

Test Start: 2005.09.19 @ 02:46:01

Tool Information

Drill Pipe:	Length:	4285.00 ft	Diameter:	3.80 inches	Volume:	60.11 bbl	Tool Weight:		2500.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	Weight set on Packer:		25000.00 lb
Drill Collar:	Length:	0.00 ft	Diameter:	2.25 inches	Volume:	0.00 bbl	Weight to Pull Loose:		80000.00 lb
					Total Volume:	60.11 bbl	Tool Chased		0.00 ft
Drill Pipe Above KB:		16.00 ft					String Weight:	Initial	64000.00 lb
Depth to Top Packer:		4297.00 ft						Final	65000.00 lb
Depth to Bottom Packer:		ft							
Interval between Packers:		102.00 ft							
Tool Length:		130.00 ft							
Number of Packers:		2	Diameter:	6.75 inches					

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths	
Change Over Sub	1.00			4270.00		
Shut In Tool	5.00			4275.00		
Hydraulic tool	5.00			4280.00		
Jars	5.00			4285.00		
Safety Joint	3.00			4288.00		
Packer	4.00			4292.00	28.00	Bottom Of Top Packer
Packer	5.00			4297.00		
Stubb	1.00			4298.00		
Perforations	2.00			4300.00		
Change Over Sub	1.00			4301.00		
Recorder	0.00	8018	Inside	4301.00		
Blank Spacing	62.00			4363.00		
Change Over Sub	1.00			4364.00		
Recorder	0.00	11084	Outside	4364.00		
Perforations	32.00			4396.00		
Bullnose	3.00			4399.00	102.00	Bottom Packers & Anchor
Total Tool Length:	**130.00**					

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior Inc.

Box 399
Garden City KS

ATTN: Scott Corsair

Shank 1-26

26-19s 22w Ness KS

Job Ticket: 22252 **DST#: 3**

Test Start: 2005.09.19 @ 02:46:01

Mud and Cushion Information

Mud Type:	Gel Chem	Cushion Type:		Oil API:	41 deg API
Mud Weight:	9.00 lb/gal	Cushion Length:	ft	Water Salinity:	ppm
Viscosity:	49.00 sec/qt	Cushion Volume:	bbl		
Water Loss:	11.19 in³	Gas Cushion Type:			
Resistivity:	ohm.m	Gas Cushion Pressure:	psig		
Salinity:	ppm				
Filter Cake:	inches				


Recovery Information

Recovery Table

Length ft	Description	Volume bbl
230.00	GOCM-5%G-40%O-55%M	3.226
50.00	Gassy oil 5%G-95%O	0.701
0.00	60 Gas in pipe	0.000

Total Length: 280.00 ft Total Volume: 3.927 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #:
Laboratory Name: Laboratory Location:
Recovery Comments:


Pressure vs. Time
8018 Pressure
8018 Temperature
Initial Hydro-static
Final Hydro-static
End Shut-In(1)
End Shut-In(2)
Shut-In(2)
Open To Flow(2)
Pressure
Temperature
2000
1750
1500
1250
1000
750
500
250
0
120
115
110
105
100
95
90
85
80
75
70
65
3AM
6AM
9AM
12PM
19 Mon Sep 2005
Time (Hours)