

36-19S-22W
NW

SCOTT CORSAIR

PETROLEUM GEOLOGIST #55

210 Avenue A P.O. Box 6
Bazine, Ks 67516
785-398-2270 Mobile 785-731-5060
FAX 785-398-2586

GEOLOGICAL REPORT

RECEIVED

MAR 31 2006

KCC WICHITA

AMERICAN WARRIOR, INC.

Williams #7
1300' FNL & 1300' FWL
Section 36-19S-22W
Ness County, KS

15-135-24395-00-00

OPERATOR: AMERICAN WARRIOR, INC.
WELL: WILLIAMS #7
API NO.: 15-135-24395
LOCATION: 1300' FNL & 1300' FWL, 36-19S-22W, NESS COUNTY, KANSAS
WELLSITE: FARMGROUND
COMMENCED: AUGUST 29, 2005
COMPLETED: SEPTEMBER 8, 2005
ELEVATIONS: 2245' GL ; 2253' KB
TOTAL DEPTH: 4370' (DRILLER); 4374' (LOG)
CASING: SURFACE: 8 5/8 @ 332' W/ 180 SKS.
 PRODUCTION: 5 1/2 @ 4364 W/ 150 SKS.
SAMPLES: 10 FT. FROM 3600' TO T.D.
LOGS: DUAL INDUCTION, DUAL COMPENSATED POROSITY & SONIC (LOG-TECH)
DRILLSTEM TESTS: NONE
CONTRACTOR: DUKE DRILLING (RIG #8)

REMARKS: Geological supervision: 3600' - T.D.

FORMATION TOPS	ELECTRICAL LOG		SAMPLES	
		SUBSEA		SUBSEA
Anhydrite	1474	+779	1473	+780
Chase	2333	-80		
Heebner	3722	-1469	3720	-1467
Lansing	3772	-1519	3769	-1516
Base KC	4101	-1848	4102	-1849
Pawnee	4188	-1935	4187	-1934
Ft. Scott	4270	-2017	4266	-2013
Cherokee	4292	-2039	4288	-2035
Mississippian	4356	-2103	4356	-2103
Total Depth	4374	-2121	4370	-2117

SAMPLE ZONE DESCRIPTION

Logger's Measurements

LANSING-KANSAS CITY 3772 -1519

There were no shows of oil/gas observed in the porous zones during the drilling of the Lansing-Kansas City section.

FT. SCOTT 4270 -2017

Limestone: Light gray to buff, crystalline, fossiliferous, poor intercrystalline porosity, very slight show of free oil, fair fluorescence, excellent cut fluorescence,

CHEROKEE 4292 -2039

There were no shows of oil/gas observed in the porous zones during the drilling of the Cherokee section.

MISSISSIPPIAN 4356 -2105

Dolomite: Tan, crystalline, sucrosic, excellent fluorescence and cut, fair show of free oil, excellent odor, **Chert:** white and translucent, angular, tripolitic, weathered, fair vuggy porosity, fair show of free oil, excellent fluorescence and cut, excellent odor.

FORMATION	American Warrior Williams #7 1300' FNL & 1300' FWL; 36-19S-22W Ness County, KS	Sinclair Oil & Gas Williams #1 NE NW 36-19S-22W Ness County, KS	Sinclair Oil & Gas Williams #1 NE NW 36-19S-22W Ness County, KS
Anhydrite	+779		
Heebner	-1469	-1464	-1468
Lansing	-1519	-1515	-1517
Ft. Scott	-2017	-2014	-2019
Mississippian	-2103	-2105	-2107

SUMMARY AND RECOMMENDATIONS

Structural position, electrical log analysis and sample examination indicate probable commercial production from the Mississippian formation, 5 1/2" casing was set 10 feet off bottom @ 4364'. The following zones are recommended for testing:


1. Mississippian: 4364-4374'

Measurements were taken from rotary kelly bushing (8 feet above ground level). Log measurements are taken as correct.

Respectfully,



Scott Corsair
Petroleum Geologist #55



2-27-06