

3:19-21

TORP

Memo

Post-It® Fax Note 7671		Date 4/1/97	# of pages 1
To	Tim Carr	From	Rodney Reynolds
Co./Dept	KGS	Co.	TORP
Phone #	cc: Paul Gerlach	Phone #	4-4491
Fax #	4-5317	Fax #	4-4967

To: Paul Wilhite
 Don Green
 Shapour Vossoughi
From: Rodney Reynolds
CC: Tim Carr
 Paul Gerlach
 Saibal Bhattacharya
Date: April 1, 1997
Re: Wellbore flowing pressures in the Schaben Field

I am in receipt of a copy of the recent fluid level data acquired by Ritchie Exploration on the wells they operate in the Schaben Field. From my experience as a production engineer, I am familiar with how this data is acquired, the instruments used to acquire this data, the accuracy limitations associated with these instruments, and how to interpret the data. My evaluation of the data indicates that of the 23 wells on which data was received, 15 of the wells are operating in a pumped off condition. This is the general practice of the oil industry, especially when dealing with marginal production. However, occasionally situations dictate that backpressure be held against the formation in wells that have high productivity, produce excessive amounts of water, to assist in reducing lifting costs, or in some instances may assist in maintaining some percentage in oil cut. I also spoke with Danny Biggs (production superintendent) and Jack Gurley (petroleum engineer) for Pickrell Drilling Company, concerning fluid levels on their wells. They indicated that they have not recently shot fluid levels, but in general they try to pump the wells off, however they have a few large water producers they cannot pump off. They said its time to shoot fluid levels and they will supply a copy of the results to me.

I have also compared the recently acquired fluid level data to the fluid level information acquired from the historic information contained in the well files, on which TORP based the model and simulation. The recent data correlates with the data we used, with 2 exceptions. The recent data indicates the Moore B-6 is carrying approx. 200' fluid above the perforations and the well files indicated it to be pumped off and the Moore D-4 which Ritchie field personnel indicated to me had "a lot of fluid in the hole" and the recent data indicates it is pumped off.

