

KANSAS DRILLERS LOG


API No. 15 — 135 — 21,214
County Number

S. 6 T. 19S R. 24 ☒ W

Loc. SW NW

County Ness

640 Acres
N



Locate well correctly
2376

Elev.: Gr.

DF KB 2383

Operator Mull Drilling Company, Inc.	
Address 415 Page Ct., 220 W. Douglas, Wichita, KS 67202	
Well No. 1	Lease Name Antenen 'C'
Footage Location 660 feet from (N) (S) line 750 feet from (E) (W) line	
Principal Contractor Blue Goose Drlg. Co	Geologist Larry Schneider
Spud Date 7-5-76	Total Depth 4440
Date Completed 7-15-76	P.B.T.D.
Oil Purchaser	

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$	8 5/8	20	246	Comm	246	3% cc 2% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Mull Drilling Company, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole		
Well No. 1	Lease Name Antenen 'C'			
S 6 T 19S R 24 E ^X W				
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.		
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale 700			Anhy	1644
Red Bed & Shale 1025			B/Anhy	1680
Anhydrite 1038			Heeb	3746
Red Bed & Snd 1376			Lans	3791
Sand & Shale 1940			B/KC	4106
Shale & Shells 2250			Pawnee	4224
Shale & Lime 3790			Ft Scott	4303
Lime 4440			Chero	4329
			B/Chero Lm	4380
			Cong Chert	4400
			RTD	4440
Dst #1 4281-4330/30-30-30-45, Wk blow 5" died, Rec 10' Mud, spts oil, ISIP 100# IFP 50#, FFP 63#, FSIP 100#, T emp 114° Dst #2 4374-4440/30-45-90-60, wk blow bldg to good blow, Rec 145' Thin Mud, 180' Mdy Wtr (90% wtr), Total Fluid 325', ISIP 1345#, IFP 63-113#, FFP 113-213# FSIP 1345#, Temp 124° NO E-LOGS TAKEN				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
Date Received	Signature Title Date			