

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


6-19-24W ✓

Company- IMPERIAL OIL CO.
Farm- Popp "B" No. 2

SEC. 6 T. 19 R. 24W
150' S CNW SW

Total Depth. 4452'
Comm. 8-28-64 Comp. 9-9-64
Shot or Treated.
Contractor. IMPERIAL OIL
Issued. 12-5-64

County Ness
KANSAS



Elevation. 2372' K.B.

8 5/8" 307' w/250 sx cem.
5 1/2" 4450' w/125 sx cem.

Production. 41 BOPD, 47 % WTR

Figures Indicate Bottom of Formations.

surface clay, sand	135
sand, shale	172
shale, shells	1023
Blaine	1033
Dakota sand	1330
shale, shells	1635
Anhydrite	1680
shale, shells	2040
shale, lime	3644
lime, chalk	3785
lime	4377
lime, chert	4450 RTD
Lime, chert	4452
Total Depth	

TOPS:	SAMPLE ELEC.
B/Blaine	1035
Anhydrite (sc)	1652 1637
B/Anhydrite ?	1680
Heebner	3738 3740
Lansing	3784 3785
Cherokee	4284 4284
Mississippian(Spergen)	4288 4391

RAN Schlumberger log,

DST # 1 - 4280-4330 Op. 2 hrs.,
rec. 60' of very slightly
OCM. ICIP 976#/20 Min. IF
19#, FF 38#, FCIP 626#/20
min.

DST # 2 - 4392-4405' Op. 2 hrs., rec
1260' gas in pipe, 250' muddy
oil. ICIP 1301#/20 min., IF 38#,
FF 96#, FOIP 1163#/20 min.