# MILLER TESTING COMPANY

Box 547

## GREAT BEND, KANSAS

Company KEDCO MANAGEMENT CORP.

Lease and Well No. LUNDY #I

County NESS State KANSAS Date OCTOBER 10, 1976

Formation Test No. I Total Depth 4382 Elev. 2319 KB

Interval Tested 4335 To 4382 Anchor Length 47'

Size Hole 7 7/8 Size Drill Pipe 4 1/2 XH and FH Size Packer 6 3/4

Mud Weight 9.5 Viscosity 44 Water Loss 8.5 c.c. Bottom Hole Temp. 116 °F

Chokes: Top 1/2 Bottom 1/2 Ticket No. 15348

Length of Drill Collar I. D. Length Flexweight 716 I. D. 2.76


### RECOVERY

WEAK INTERMITTENT BLOW FOR 15 MINUTES.

20 FEET OF MUDDY WATER WITH OIL SPOTS.

Lease and Well No. LUNDY #I 33 19S 24 W SE SE SW

Formation Test No. I




Tool Open: 1st Flow ___ hr. 30 mins: Shut-in Initial ___ hr. 30 min: 2nd Flow ___ hr. 30 min: Shut-in Final ___ hr. 30 m

| | Field Reading | Corrected Reading |
|---|---|---|
| (A) Initial Hydrostatic Pressure | 2237 | 2257 |
| (B) Initial 1st Flow Pressure | 81 | 75 |
| (C) Final 1st Flow Pressure | 81 | 79 |
| (D) Initial Shut-in Pressure | 101 | 97 |
| (E) Initial 2nd Flow Pressure | 81 | 81 |
| (F) Final 2nd Flow Pressure | 81 | 81 |
| (G) Final Shut-in Pressure | 101 | 93 |
| (H) Final Hydrostatic Pressure | 2227 | 2227 |

15348

# MILLER TESTING COMPANY

Box 547

## GREAT BEND, KANSAS

Company KEDCO MANAGEMENT CORP.

Lease and Well No. LUNDY #I

County NESS State KANSAS Date OCTOBER 11, 1976

Formation Test No. 2 Total Depth 4398 Elev.

Interval Tested 4384 To 4398 Anchor Length 14'

Size Hole 7 7/8' Size Drill Pipe 4 1/2 FH and XH Size Packer 6 3/4

Mud Weight 9.5 Viscosity 44 Water Loss 8.5 c.c. Bottom Hole Temp. 116 °F

Chokes: Top 1/2 Bottom 1/2 Ticket No. 15349

Length of Drill Collar I. D. Length Flexweight 716 I. D. 2.76


### RECOVERY

WEAK BLOW DEAD IN 25 MINUTES.
FLUSHED TOOL ON SECOND OPENING.
GOOD SURGE NO BLOW.

20 FEET OF SLIGHTLY OIL CUT WATERY MUD.

Lease and Well No. LUNDY #I 33 19S 24W SE SE SW

Formation Test No. 2




Tool Open: 1st Flow ___ hr. 30 mins: Shut-in Initial ___ hr. 30 min: 2nd Flow ___ hr. 30 min: Shut-in Final ___ hr. 30 mir

| | Field Reading | Corrected Reading |
|---|---|---|
| (A) Initial Hydrostatic Pressure | 2276 | 2277 |
| (B) Initial 1st Flow Pressure | 60 | 63 |
| (C) Final 1st Flow Pressure | 60 | 63 |
| (D) Initial Shut-in Pressure | 946 | 942 |
| (E) Initial 2nd Flow Pressure | 40 | 45 |
| (F) Final 2nd Flow Pressure | 40 | 45 |
| (G) Final Shut-in Pressure | 707 | 709 |
| (H) Final Hydrostatic Pressure | 2266 | 2257 |

15349

# MILLER TESTING COMPANY

Box 547

## GREAT BEND, KANSAS

Company KELCO MANAGEMENT CORPORATION

Lease and Well No. LUNDY #I

County NESS State KANSAS Date OCTOBER 11, 1976

Formation Test No. 3 Total Depth 4406 Elev. 2319 KB

Interval Tested 4393 To 4406 Anchor Length 13'

Size Hole 7 7/8 Size Drill Pipe 4 1/2 FH and XH Size Packer 6 3/4

Mud Weight 9.5 Viscosity 45 Water Loss 10.2 c.c. Bottom Hole Temp. 116 °F

Chokes: Top 1/2 Bottom 1/2 Ticket No. 15350


Length of Drill Collar 29 I. D. 2.25 Length Flexweight 747 I. D. 2.76

### RECOVERY

WEAK BLOW. DEAD IN 5 MINUTES.
FLUSHED TOOL ON SECOND OPENING.
GOOD SURGE NO BLOW.

65 FEET OF SLIGHTLY OIL CUT MUDDY WATER.

Lease and Well No. LUNDY #I 33 19S 24 W SE SE SW Formation Test No. 3




Tool Open: 1st Flow ___ hr. 30 mins: Shut-in Initial ___ hr. 30 min: 2nd Flow ___ hr. 30 min: Shut-in Final ___ hr. 30 mi

| | Field Reading | Corrected Reading |
|---|---|---|
| (A) Initial Hydrostatic Pressure | 2276 | 2277 |
| (B) Initial 1st Flow Pressure | 60 | 69 |
| (C) Final 1st Flow Pressure | 60 | 69 |
| (D) Initial Shut-in Pressure | 1065 | 1065 |
| (E) Initial 2nd Flow Pressure | 81 | 71 |
| (F) Final 2nd Flow Pressure | 81 | 71 |
| (G) Final Shut-in Pressure | 926 | 928 |
| (H) Final Hydrostatic Pressure | 2266 | 2247 |

15350