

McCoy Petroleum Corporation
Omaha Hotel "M" #2-4
NW NW SW
Section 4-19S-25W
Ness County, Kansas
API #15-135-24,083

ACO-1 Continued

DRILL STEM TESTS:

DST #1 4400'- 4445' (Mississippian Dolomite)

Open 30", SI 60", Open 60", SI 90"

1st Open: Weak to strong blow OBB in 19 min. Weak surface blow back on initial SI.

2nd Open: Weak to strong blow OBB in 21 min.

Recovered: 300' GIP

423' Clean Gassy Oil (20% gas, 80% oil) (Gravity 37° API)

300' Gassy Mud-cut Oil (25% gas, 45% oil, 30% mud)

FP: 45-145 / 168-280#

SIP: 1253-1253#

LOG TOPS:

Anhydrite	1746(+717)
Base Anhydrite	1785(+678)
Heebner	3804(-1341)
Lansing	3847(-1384)
Stark	4090(-1627)
Marmaton	4195(-1732)
Pawnee	4276(-1813)
Ft. Scott	4349(-1886)
Cherokee	4372(-1909)
Mississippi	4435(-1972)
RTD	4445(-1982)
LTD	4445(-1982)