

Date	Depth	
	3212	Brown Lime (-1322)
	3225	Kansas City (-1335)
5/31 D.S.T. #1	- 3262-85'	- Op 1 hr., SI 25", wk. bl. died in 7", flushed tool 10" open, Rec. 15' mud slt oil-specked, SIP 35-75#, FP 20-20#
	D.S.T. #2	- 3282-96' - Op 30", wk. blow died in 5", Rec. 10' mud, SIP 75-50#, FP 25-35#
	3380	Circ. (Preparing to test)
6/1 D.S.T. #3	- 3350-80'	- Op 30", wk. bl. died in 5", Rec. 10' mud, SIP (20") 1030-475#, FP 30-40
	D.S.T. #4	- 3401-19' - Op 90", Rec. 75' mdy salt water, SIP (20") 1210-850#, FP 20-60#
	3430	Drig.
	D.S.T. #5	- 3470-3523' - Op 30", wk. bl. died in 7", Rec. 15' mud, SIP (20") 435-145#, FP 45-60#
	3513	Conglomerate
	3549	Arbuckle (-1659) (20' lower than offset)

State **Kansas** County **Barton**


Company **E.H. Riggs** Well No. **1**

Farm **Schumacher**

Survey

Block No. Sec. **27** Twp. **19 S** Range **14 W**

Co-Ord. Elev. **1890' R/B**



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line		Ft. from S. Line
Ft. from W. Line		Ft. from E. Line
Date	Depth	
	D.S.T. #6 - 3550-59' - Op 20', wk. bl.	
	died in 4", Rec. 5' mud,	
	BHP 940-420#, FP 20-30#	
	D.S.T. #7 - 3559-84' - Op 1 hr., Rec.	
	100' gas, 2440' salt wtr.,	
	BHP (20") 1160-1100#,	
	FP 145-670#,	
	D & A 6/3/61	