

13-1943W ed
 Albert Wheeler

Plotted Texas CO.


THE DICKEY OIL COMPANY.
 Tull No. 1.

SEC. 13 T. 19 R. 3W.
 NEc SW

County. McPherson.

Total Depth. 3006
 Comm. 10-1-34 Comp. 12-31-34
 Shot or Treated.
 Contractor.
 Issued. 2-16-35.

FEB 16 1935



CASING.

20" 80' 8 1/2" 2562' UR 2957
 15 1/2" 387' 65/8" 2980'
 10" 2271' UR2325

Elevation.

Production. Pot. 756 B.

Figures Indicate Bottom of Formations.

sand yellow	38	lime	1300	shale	2760
sard yellow	70	red rock 4 BW	1320	lime	2803
shale blue	80	shale	1350	slate blk	2808
shale	115	red rock	1360	shale & shells	2835
red mud	155	slate white	1375	shale	2840
shale blue 1/2 BW	230	shale	1390	lime	2863
lime	238	lime	1393	shale	2880
shale blue	387	shale blue	1400	lime	2890
shale white	415	shale blk	1420	shale	2915
shale white	425	lime	1435	shale & shells	2935
lime shells	430	mud red	1440	shale	2940
shale blue	450	shale blue	1475	variegated shale	2945
lime	475	shale blue 2 BW	1495	shale grey	2957
shale	480	lime	1520	chat	2973
lime shells	495	shale blue	1560	5,000,000 dry gas	2973
lime	540	lime	1575	2957 to 2975	3,500,000 gas.
shale & shells	560	red rock	1578	increase gas	1,500,000
red rock	570	lime	1585	chat oil	2987
lime	615	red rock	1590	very heavy spray	
shale	625	lime	1610	45' above floor.	
red rock	630	shale blue	1624	chat	3006
lime	675	shale brown	1655	Total Depth.	
shale blk	680	7 BW 1640		gas and oil increase	2997-
lime	770	shale blue	1665		3005
red rock	790	lime	1735		
shale light	800	shale blue 5 BW	1785		
shale blue	820	lime	1870		
lime	855	shale blue	1875		
shale	860	lime	1920		
lime	880	shale grey	1940		
red rock	885	lime 9BW 2035	2100		
red rock	895	shale blue 5BW	2105		
lime	900	lime HFW	2130		
slate & shells	920	broken lime	2140		
lime	975	sard and lime	2150		
shale blue	990	sand	2185		
lime	995	gritty lime	2230		
shells and slate	1020	shale	2245		
red rock	1025	shale blue	2278		
lime 3 BW	1045	lime	2285		
sand	1053	red rock	2293		
lime	1075	lime	2300		
shale	1085	shale HFW	2330		
lime shells	1125	K.C. lime 10 BW	2470		
lime	1170	oil at 2340- 1 1/2 BW.			
shale	1175	8 B. oil at 2420 6 BW			
shale blk	1210	sand and lime	2490		
shale white	1225	lime hard HFW	2598		
shale	1240	shale	2603		
lime	1245	lime	2685		
shale blue	1260	2 1/2 BW 2650			
lime	1265	shale & shells	2705		
shale	1275	shale & shells	2724 3 BW		
red rock	1290	shale	2740		
shale brown	1295	lime	2750		

Deepened by Standind

Leasing 2330
 Miss. 2957

OWPB 2/12/1947
 6" 2980 PB 2358
 Perf 60 sh 2331-46
 1000 A
 P 9 B0 & 35 BW PD
 (Chindberg)