


KANSAS GEOLOGICAL SOCIETY  
508 East Murdock  
Wichita, Kansas

AUG 30 1969



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS

67460

May 8, 1969

35-19S-3W  
NE 1/4 NW 1/4  
ORIGINAL

K C C

JUN 30 1993

COMPANY: LITAN & WARNER  
CONTRACTOR: BLACKSTONE DRILLING, INC.  
FARM: KASEY # A-2  
LOCATION: NE/4 NW/4 NW/4, Sec. 35-19S-3W,  
McPherson County, Kansas  
COMMENCED: May 2, 1969  
COMPLETED: May 7, 1969  
ELEVATION: *Oil*

|      |    |      |                |
|------|----|------|----------------|
| 0    | to | 70   | Shale          |
| 70   | to | 100  | Sand           |
| 100  | to | 158  | Shale & Shells |
| 158  | to | 745  | Shale & Lime   |
| 745  | to | 980  | Lime           |
| 980  | to | 1815 | Shale & Lime   |
| 1815 | to | 2735 | Lime           |
| 2735 | to | 2947 | Lime & Shale   |
| 2947 | to | 3050 | Mississippi    |
|      |    | 3050 | T. D.          |

Cut 12 1/4 in. hole to 158 ft. and run 160 ft. of 8 5/8 in. surface casing, cemented with 115 sacks cement on bottom at 158 ft. Plug down at 2:00 P.M., May 2, 1969. Cut 7 7/8 in. hole to 3050 ft. and run 3051 ft. of 5 1/2 in. casing and cemented with 50 sacks on bottom at 3050 ft. Plug down at 12:30 P.M., May 7, 1969.

TOPS: Mississippi - 2947'

Measurements taken from K.B.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 09 1993

CONSERVATION DIVISION  
WICHITA, KS

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is and true and correct copy of log on your Kasey #2-A, located on the NE NW NW, Sec. 35-19S-3W, McPherson County, Kansas as reflected by the files of BLACKSTONE DRILLING, INC.

*H. J. Plouffe*  
H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 22 day of May, 1969.

*Ruth McVay*  
Ruth McVay - Notary Public

Expires: December 18, 1969.



K. G. S. LIBRARY