

12/14/90
RELEASED

JAN 03 1992

3-19-30W

DRILLER'S WELL LOG

FROM CONFIDENTIAL

DATE COMMENCED: 11-03-89
DATE COMPLETED: 11-11-89

SLAWSON EXPLORATION COMPANY, INC.
BRYANT "J" #1
NE NE SW Sec. 3-19S-30W
Lane County, Kansas

Elevation: 2876 GR 2881 KB

FORMATION DATA: (Sample)

0 - 350 clay & shale
350 - 1170 clay & shale
1170 - 1800 shale & sand
1800 - 1934 sand
1934 - 2202 shale W/lime
2202 - 2220 anhydrite
2220 - 2855 shale/lime
2855 - 4647 Lime & shale
4647 R.T.D.

Anhydrite top 2201 (+680)
Anhydrite base 2219 (+662)
Wabunsee 3513 (-632)
Topeka 3694 (-813)
Heebner 3909 (-1028)
Lansing 3950 (-1069)
Muncie Creek 4139 (-1258)
Stark 4239 (-1358)
Hushpuckney sh 4276 (-1395)
Middle Creek 4279 (-1398)
BKC 4318 (-1437)
Altamont 4369 (-1488)
Pawnee 4446 (-1565)
Ft. Scott 4494 (-1613)
Lower Cherokee 4519 (-1638)
Johnson 4453 (-1672)
Mississippi 4575 (-1694)
R.T.D. 4647 (-1766)

Surface Casing:

8 5/8" set @ 347' W/180 sx. 60/40
Pozmix, 2% Gel, 3% CC

CONFIDENTIAL

DEC 18 1989

KANSAS GEOLOGICAL SURVEY
WICHTA BRANCH


A I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON)ss

GREG DAVIDSON of lawful age, does swear and state that the facts and statements
herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 14th day of November 1989.



Bessie M. DeWerff
Bessie M. DeWerff: Notary Public

My Commission expires: 5-20-93