



PHONE BR 4-1301

1404 SOUTH CEDAR

BORGER, TEXAS

DRILLING REPORT

Wise #1
NW-NW-SE
S6-19S-31W
Scott County, Kansas

8-26-66

Murfin Drilling Company moved in and spudded. Drilled 12 1/4" hole to 250 feet ground level. Run 238 feet 8 5/8" pipe and set at 240 feet ground level. Cemented with 185 sacks Common Cement, 3% Calcium Chloride. Cement circulated.

8-28-66

Drilling at 2285'.

8-29-66

Drilling at 2820'.

8-30-66

T.D. 2825 feet - Ran Schlumberger Log - Ran 85 joints 4 1/2" pipe, 9 1/2 lbs. - 2832 feet - set at 2825 feet. Cemented with 100 sacks salt saturated Common Cement. Plug down at 9:15 p.m. on August 29, 1966.

8-31-66

Waiting on cement.

9-1-66

Run temperature survey - shows top of cement 2415 feet - T. D. reached 2820' - Waiting on cement.

11-28-66

Run correlation log. Perforated 4 holes at 2768 feet. Swabbed down pipe. Show of gas.

11-29-66

Load hole with 3 per cent acid and CO₂. Break down 2200 pounds. Fracked with 20,000 gallons 3 per cent and 10,000 pounds sand and CO₂. 15 BPM at 2100 pounds. Started blowing well back at 11:20 A. M.

11-30-66

Well dead. Preparing to swab. Well complete.