

5-29W

MAP NO. _____

SEC. 18-19S-31W

STATE Kans COUNTY Scott

LOC. C SW SW

OPER. Leo J. Dreiling Oil Co., Victoria, Kansas

FT/FR _____ LINE

WELL 1 FARM Yeager

FT/FR _____ LINE

Wildcat ELEV. 2967 GR. 2969 DF 2972 KB


CO. tools GEOL. Charles Steincamp

INT. NCRA & Mobil Support - 4800' Miss Test

F.R. 4-15-63 SPUD 4-16-63 COMP. 5-7-63

TD 4700 FM. Mississippian PBD.

D&A



COMP RECORD

8" @236 w/135 sx.

WC-3 1/2 miles SW of Abd Miss & Viola oil in Grigston field *Dale Inc.*

(KB Spl)

(KB Log)

Hb	3902	Hb	3901	- 929
Lans	3947	Lans	3949	- 977
RTD	4700	BKc	4364	-1392
		Marm	4378	-1406
DST #1 (Lans) 3981-4020, Op 45",		Paw	4428	-1456
R 2425' Sult wtr, ISIP 1104#/ 30", IFP 832#, FFP 1104#,		FS	4464	-1492
FSIP 1104#/30"		Chero	4473	-1501
DST #2 (Lans) 4257-4332, Op 1		Miss	4604	-1632
		LTD	4700	-1728

hr, R 2500' SW, ISIP 1209#/30", IFP 1213#, FFP 1209#, FSIP 1219#/30", RTD 4700, Log, D&A COMPLETED (4-30-63)

KR1 7230

AMARILLO TOPS

2972 KB

Heebner 3905 (-933)

Lansing 3949 (-977) tst 2425' Sulf wtr; tst 2500' XW

Marmaton 4375 (-1403)

St. Louis 4604 (-1632)

TD 4701 D & A