

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

26-19-33W

COMPANY **YUCCA PETROLEUM**

SEC. 26 T. 19 R. 33W
 LOC. C SE NW

FARM **Smith**

NO. **1**

COUNTY **Scott**

TOTAL DEPTH **4987'**


COMM. **7-9-68**

COMP. **7-27-68**

SHOT OR TREATED

CONTRACTOR **Leben Drlg.**

ISSUED **10-12-68**



CASING

20 10
 15 8 5/8" 368' cem w/ 280 sx

12 6
 13 5
 4 1/2" 4850' cem w/ 200 sx

FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION **2967' KB**

PRODUCTION **P 256 BOPD, NW**
ST Lou 4654-59 4670-75,
Gr 26

0	180	Surface Soil, Sand and Gravel
180	371	Shale
371	1030	Shale, Sand
1030	2173	Shale, Red Bed
2173	2193	Anhydrite
2193	2270	Shale, Shells
2270	3070	Shale, Lime
3070	3850	Lime, Shale
3850	4465	Lime
4465	4505	Lime, Chert
4505	4630	Lime
4630	4688	Core #1
4688	4820	Lime, Chert
4820	4878	Core #2
4878	4987	Lime, Chert
	4987	RTD Set 4 1/2" casing

TOPS: SMP

Base Fort Hays	390
Base Anhydrite	2188
Tarkio	3410
Heebner	3813
Lansing	3850
Base Kansas City	4273
Marmaton	4297
Cherokee	4418
Mississippi	4624
Spargen	4811
Osage	4946
LTD	4987

 casing Set @ 368' with 280 sacks Common

I hereby certify that the above and foregoing is
 a true and correct copy of the log of the Smith #1 well, located
 in Township 19 South, Range 8 West, Scott
 County, Kansas, as recorded by the records of Leben Drilling, Inc.

Leslie Kite